

# **DEENDAYAL PORT AUTHORITY**



Office of the Executive Engineer,  
Harbour Division, Nirman Building,  
New Kandla (Kutch), Gujarat-370210.

Tel : (02836) 270325

Email ID: - [kphdivision@gmail.com](mailto:kphdivision@gmail.com)

Dated: 22.05.2023.

No:-HW/WK/EOI/2700/

To, M/s

## **Expression of Interest**

Sub: - "Modification & Upgradation of existing godown no 18 & 24 inside cargo jetty area"

Sir,

Deendayal Port Authority intends to invite e-tender for the subject work.

Kindly submit your Expression of interest along with budgetary-offer for the subject work on the basis of tentative requirements of material enclosed herewith.

The rates quoted must be inclusive of all taxes, & exclusive of GST.

Your budgetary offer for the above work should reach to the above mentioned address on or before 31.05.2023.

Thanking you,

Encl. As above

Yours faithfully,

Executive Engineer  
Deendayal Port Authority

**Sub: Budgetary offer for the work of**

" Modification & Upgradation of existing godown no 18 & 24 inside cargo jetty area "

Sr. No.	Description of Item	Qty	Rate	Unit	Amount
1	<p>Providing and fixing of Self Supported Structure Less Roofing systems with proper overlapping and seaming between different sheets without making holes or preventing the overturning the roof by wind addition made up from Regular Modified Polyster Imported Color Coated Galvalume Cold Rolled Structural Steel Sheet Coils of superior quality structural steel of Grade D. Base metal width 912 mm, and Thickness 1.60 mm BMT, 1.65 mm APT with tolerance of +/- 0.04 mm, Profiled width of 625 mm +/- 10mm.</p> <p>Design, supply, &amp; fabrication of self supported single span arch roof fabricated from mechanically seamed manufactured by American Machines to profiles as per standard ASTM A792, Steel Sheet, Aluminum-Zinc Alloy Coated by Hot-Dip Process. The work should be carried out by specialize and approved agency only. The rate of item is including fitting as per standard specification.</p> <p>(Note: Only plan area of sheet to be measures i.e. clear length without corrugation &amp; curved/sloping width. No extra measurements/ payments shall be given for corrugation/profile &amp; over lapping. The area of skyligh sheet/turbo ventilators will be deducted.)</p> <p>(A) For main roof of 22.50 m span (B) Length 156m &amp; 138m (C) Arch Rise 6.43m (D) Arch Length 28.13m (E) No of Bays 2 No. (F) Building Height 6m</p>	16540.00		M <sup>2</sup>	

