



DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer (TD),
Room No.125, Annexe,
Administrative Office,
Gandhidham – Kutch, Pin – 370 201
E – Mail: tddivisionkpt@gmail.com

No :- TW/WK/7858/1371
Date: 18/10/2023

To,

Expression of Interest.

Sub: - S/R to Sports Complex at Port Colony Gopalpuri, Gandhidham..

Sir,

Deendayal Port Authority intends to carry out the subject work of TD Division of Civil Engineering Department for a period of six months.

Kindly submit your Expression of Interest along with budgetary offer for the items considered in preparation of the estimate under **Annexure-I**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of Interest along with budgetary offer for the above work should reach to the following address on or before 25/10/2023 by 15:00 Hrs.

Address:-

Office of the Executive Engineer (TD),
T.D. Division, Administrative Office Building,
Ground floor, Room No.105, Annexe,
P.O. Box No. 50, Gandhidham – Kachchh.
Email: tddivisionkpt@gmail.com

Thanking you,

Yours faithfully,

Executive Engineer (TD)
Deendayal Port Authority

Annexure - I				
Sr. No.	DESCRIPTION	UNIT	RATE	
			In Figure	In Words
	PART -A Execution			
1	Football Ground			
A	Refurbishment of the base etc. for Installation of synthetic artificial turf for a football field from a FIFA preferred provider as per tender(9690 M2).	M2		
B	Supply and Installation of synthetic artificial turf for a football field from a FIFA preferred provider having finger unit coating permeable backing, pile height 50mm, polyethylene slit filament, fire retardant, certified lead free, including customs clearance, insurance, infill comprising of rubber (0.85 kg/sft) and silica sand (2.4kg/sft). The proposed brand needs to be from America/Europe/Australia origin only. The agency also needs to provide unloading and staging of rolls, sewing of seams, infilling with appropriate dispensing, spreading and levelling equipment, brushing of fibres with all poly-hydraulic controlled equipment as directed by Engineer in charge(9690 M2).	M2		
2	Athletic Track			
A	Refurbishment of the base etc. for Installation of synthetic athletic track all complete as per requirements/specifications laid down by World Athletics (IAAF) preferred provider including UV Seal Coating(3200 M2).	M2		
B	Supply and Installation of synthetic athletic track including markings on the surface all complete as per requirements/specifications laid down by World Athletics (IAAF) from a firm who had previously supplied and installed the original cast in-situ athletic track(3200 M2).	M2		
	PART - B Credit item			
3	Removal of existing football turf, Surface dressing of the ground including removing and disposal of same & transportation. The new installation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as directed by Engineer in charge(9690 M2).	M2		
4	Removal of existing synthetic athletic track, Surface dressing including removing and disposal of same & transportation. The new installation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as directed by Engineer in charge(3200 M2).	M2		