

## **SCHEDULE - A**

**Name of Work: AMC for White Washing, Distempering, Painting to Residential and Non - Residential Building at Gopalpuri, Gandhidham and Adipur for a year**

Item No.	Description	Qty.	Rate		Unit		Place of Delivery
			In figure	In word	In figure	In word	
1	Cement	18.09			1 MT	One metric tonne	Brought by contractor

Note: The above quantity is tentative

**Contractor**

**EXECUTIVE ENGINEER (TD)**  
**DEENDAYAL PORT AUTHORITY**

### **BILL OF QUANTITY (Schedule - B)**

<b>Name of Work :- AMC for White Washing, Distempering, Painting to Residential and Non - Residential Building at Gopalpuri, Gandhidham and Adipur for a year</b>						
<b>Sr. No.</b>	<b>Description of Item</b>	<b>Quantity</b>	<b>Rate</b>	<b>Unit</b>	<b>Amount (In Figures)</b>	<b>Amount (In Words)</b>
<b>1</b>	White washing with lime to give an even shade: work (one or more coats) wall Compound wall of Quarters (A)Old Internal Fencing	<b>74400.00</b>	8.12	M2	₹ 604,128.00	Rs. Six lakhs Four thousand One hundredTwenty Eighty only
<b>2</b>	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	<b>13282.76</b>	11.45	M2	₹ 152,087.54	Rs. One lakh Fifty Two Thousand Eighty seven and fifty four paise only
<b>3</b>	Repair to plaster of thickness 12mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	<b>2010.00</b>	378.25	M2	₹ 760,282.50	Rs. Seven lakh sixty thosuan and two hundred eighty two and fifty paisa only
<b>4</b>	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	<b>17232.92</b>	150.01	M2	₹ 2,585,109.58	Rs. Twenty Five Lakh Eighty Five Thousand One hundred nine and fifty eight paise only
<b>5</b>	Distempering with 1st quality acrylic distemper (ready made) having VOC content less than 50 gm per ltr. of approved manufacturer and of required shade and colour complete. as per manufacturer's specification.	<b>58892.18</b>	35.42	M2	₹ 2,085,960.87	Rs. Twenty lakh eighty five thousand nine hundred sisty and eighty seven pase only eighty six thousand twenty four and eighty four paisa only
<b>6</b>	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour	<b>14659.38</b>	85.09	M2	₹ 1,247,366.64	Rs. Twelve lakh Fourty seven thousand three hundred sisty six and sisty four paise only

Sr. No.	Description of Item	Quantity	Rate	Unit	Amount (In Figures)	Amount (In Ward)
7	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : (A) Two or more coat on old work	27071.75	60.59	M2	₹ 1,640,277.33	Rs.Sixteen lakhs fourty thousand two hundred seventy seven and thirty three paisa only
8	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content.					
(a)	With ready mixed pink or grey primer on wood work (hard and soft wood) having VOC content less than 50 grams/ litre	630.00	43.015	M2	₹ 27,099.45	Rs.Twenty seven thousand ninety nine and fourty five paisa only
(b)	With ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works	1350.00	38.85	M2	₹ 52,447.50	Rs. fifty two thousand four hundred fourty seven and fifty paise only
(c)	With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	2010.00	45.12	M2	₹ 90,691.20	Rs. Ninety thousand six hundred ninety one and twenty paise only
9	Floor painting with floor enamel paint of approved brand and manufacture of required colour to give an even shade : (A) One or More coat on Old work	2655.00	60.00	M2	₹ 159,300.00	Rs. One lakh fifty nine thousand three hundred only
10	Painting with silicon & acrylic emulsion based water thinnable sealer of approved brand and manufacture on wet or patchy portion of plastered surfaces : (A) One or more coats on old work	14659.38	58.45	M2	₹ 856,840.76	Rs. Eight lakh fifty six thousand eight hundred fourty and seventy six paisa only
11	Finishing walls with water proofing cement paint of required shade : (A) Old work (one or more coats @ 2.20 kg/10 sqm) complete.	12490.64	44.28	M2	₹ 553,085.54	Rs.Five lakh fifty three thousand eighty five and fifty four paise only
12	Finishing walls with Acrylic Smooth exterior paint of required shade : (A) Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm)	29471.00	52.32	M2	₹ 1,541,922.72	Rs. Fifteen lakh Fouty one thousand nine hundred twenty two and seventy two paise only
13	Crack repairing of Buildings, Quarters, inside and outside at any height with required material like cement, SBR, making 'v'groom, filled it with rich cement , SBR, nearu etc. all cup with all labour tools & plants etc all complete by Engineer-in-charge	3150.00	150.00	RMT	₹ 472,500.00	Rs. Four lakh seventy two thousand five hundred only

Sr. No.	Description of Item	Quantity	Rate	Unit	Amount (In Figures)	Amount (In Words)
14	Polishing on wood work with ready mixed wax polish of approved brand and manufacture : (A) Old work	312.00	58.07	M2	₹ 18,117.84	Rs.Eighteen thousand one hundred seventeen and eighty four paise only
15	French spirit polishing : (A) One or more coats on old work	3600.00	129.78	M2	₹ 467,208.00	RS. Four lakh sixty seven thousand two hundred eight only
<b>Total</b>					<b>₹ 13,314,425.00</b>	
I / We am/are willing to carry out this work at _____ % above/below (percentage should be written in figure and words). The tendered rates mentioned above amount of my / our tender are put as under:-						
Estimated amount put to tender Rs. _____		Estimated amount put to tender Rs. _____				
Deduct _____ % below (-) Rs. _____		Add _____ % above (+) Rs. _____				
Net Rs. _____		Net Rs. _____				
_____ )		_____ )				
<b>CONTRACTOR</b>		<b>EXECUTIVE ENGINEER (TD) DEENDAYAL PORT AUTHORITY</b>				