


# दीनदयाल पोर्ट प्राधिकरण

## DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer (H),  
Harbour Division, Nirman Building  
New Kandla- 370201  
Kachchh (Gujarat)  
Email: [kphdivision@gmail.com](mailto:kphdivision@gmail.com)  
[www.deendayalport.gov.in](http://www.deendayalport.gov.in)

\*\*\*\*\*

No: HW/WK/2615

Date: 29/01/2024

To,

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

### Expression of Interest.

**Sub:- Two Years Maintenance Contract for Non-Residential buildings inside Harbour Area (Civil Work)**

R/Sir,

Deendayal Port Trust intends to carry out the subject work of Harbour Division of Civil Engineering Department for a period of 24 months.

Kindly submit your Expression of Interest along with budgetary offer for the items considered in preparation of the estimate under **Annexure-A**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work, Contractor's Profit. The rates shall be exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your expression of interest along with budgetary quotation for the above work should reach to the following address on or before 05/02/2024 by 15:00 Hrs.

**Address:-**

Office of the Executive Engineer (H),  
Harbour Division, First Floor,  
Nirman Building, New Kandla,  
Kutchh (Gujarat)  
Email : [kphdivision@gmail.com](mailto:kphdivision@gmail.com)

Thanking you,

Yours faithfully,

Sd/-

**Executive Engineer (H)**  
**Deendayal Port Authority**

**BUDGETARY QUOTATION**

**Name of Work : Two Years Maintenance Contract for Non-Residential buildings inside Harbour Area (Civil Work)**

Sr.No.	Description	Quantity	Unit	Rate
1.	Poly Carbonate Sheet 6 mm thick	100.00	Sq.m	
2.	Full body Vitrified Tiles	10.00	Sq.m	
3.	Repairing , Rewinding, Servicing of monoblock/ submercible water pumps various capacity including removing and Refixing and replacement of all the required spare parts i.e. mortar winding, capacitor, bearing etc. complete as directed by Engineer-In-Charge.			
	(a) 0.5 HP to 1 HP Capacity	10.00	Each	
	(b) 2 HP to 3 HP Capacity	10.00	Each	
4.	Supplying & fixing of monoblock motor pump of different capacity of approved quality with necessary fittings, making electrical connections, testing etc. complete as directed by the Engineer In-charge			
	(a) 0.5 HP Capacity	4.00	Each	
	(b) 1 HP Capacity	6.00	Each	
	(c ) 2 HP Capacity	3.00	Each	
	(d ) 3 HP Capacity	3.00	Each	
5.	Providing & fixing SWR PVC (I.S.I - IS 13592) waste or vent pipe including necessary specials such as Tees, Bends, Y's Plinth offsets, Shoes , Vent cowl etc. with bracket , screws on wooden plugs fixed on wall face including filling joints with solution & cement mortar 1:2 complete as directed.			
	(a) 75 mm dia. (Outer Dia)	50.00	Rmt	
	(b) 110 mm dia. (Outer Dia)	50.00	Rmt	
6.	Supplying & fixing the following fixtures of Stainless Steel of approved quality to the doors, windows, ventilators etc. complete as directed by Engineer-in-Charge.			
	(a) Handle 100 mm size.	20.00	Each	
	(b) Aldrop 300 x 16 mm size	10.00	Each	
	(c ) Mortice Lock (handle)	10.00	Each	
7.	Operating of various capacity water pumps for pumping of fresh water from under ground water tanks to overhead water tanks at various location of office buildings including operating of valves by Deputing Operator or manpower with necessary Transportation Vehicle and communication means etc.. as directed by Engineer-In-Charge.			
	6 Location X 670 Days = 4020 Location per Days	4020.00	Location per Days	
8.	Deployment of Tractor with tractor trolly including labours for removing of solid waste// Garbage/Debrish material and disposing the same outside of cargo jetty area. The rates are including tractor trolly and labours, loading, unloading & lead upto 3 Km out side cargo jeetty area.	200.00	Trip	

**Note :** The rates are excluding of GST.

**Signature of Contractor  
with seal**

**Place :** \_\_\_\_\_

**Date :** \_\_\_\_\_ -

Sd/-  
**EXECUTIVE ENGINEER (H)  
DEENDAYAL PORT AUTHORITY**