



दीनदयाल पत्तन प्राधिकरण
DEENDAYAL PORT AUTHORITY
अपतट तेल टर्मिनल विभाग
Off-Shore Oil Terminal Department

प्रशासनिक भवन A.O. Building,
वाडिनार Vadinar – 361 010,
जिला: देवभूमि द्वारका (गुजरात),
Dist. Devbhoomi Dwarka (Gujarat),
दूरध्वनी Phone No. : +91-2833-257301
Email : com@deendayalport.gov.in

NO.OOT/C/166/Quotation/2023/

Date:- 21.02.2024

Quotation

To,

Name of Work:- Repairing work of Car Parking Shed & Main gate at Jetty, Vadinar.(R/m of Non-Residential building & Operational building at Jetty, Vadinar)

Sealed quotation are invited from the intending contractors and piece workers for following items up to 15:00 hrs on 28.02.2024 date & the same will be opened by the Executive engineer (c) on the same day at 16:00 hrs.

| No. | Description | Qty. | Rate | Unit | amt. |
|-----|--|-------|---------|------|------|
| 1 | Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. | 0.76 | 200.8 | m3 | 153 |
| 2 | Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size). | 1.32 | 5561.96 | m3 | 7342 |
| 3 | Centering and shuttering including strutting, propping etc. and removal of form for all heights :Foundations, footings, bases of columns, etc. for mass concrete | 7.02 | 215.57 | m2 | 1513 |
| 4 | Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position: Thermo-Mechanically Treated bars of grade Fe-500 or more. | 99.15 | 62.76 | Kg | 6223 |
| 5 | 15 mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix :1:4 (1 cement: 4 fine sand) | 8.91 | 284.27 | m2 | 2533 |
| 6 | Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturer's specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm , | 8.91 | 111.27 | m2 | 991 |
| 7 | Painting Steel/wood work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture | 78.91 | 98.04 | m2 | 7736 |

| | | | | | |
|----|---|---------|--------|----|---------------|
| 8 | Steel work welded in built up sections/ framed work,including cutting,hoisting, fixing in position and applying a priming coatof approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder,MS holloow pipe,G.I.pipe, railings,brackets, gates etc and similar work (Rate is exclusive cost of primer) | 1788.67 | 98.18 | Kg | 175612 |
| 9 | Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of thesheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixing with polymer coated J, or L hooks, bolts andnuts 8 mm dia. G.I. plain and bitumen washers or with self drilling fastener and EPDM washers and with EPDM seal etc.complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. | 113.75 | 407.09 | m2 | 46306 |
| 10 | Providing and fixing stainless steel (Grade 304) railing/gate made of Hollow tubes, channels,plates etc., including welding,grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.). | 518.65 | 428.58 | Kg | 222283 |
| 11 | Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave,holdfasts etc. complete and stacking within 50 metres lead :Of area beyond 3 sq. metres | 41.91 | 290.19 | m2 | 12162 |
| | Total amt. | | | | 482854 |

I/we am/are agree to execute the work

at _____% above (In figure), _____% above(In words)

at _____% below (In figure), _____% below(In words)

Sign of Contractor

Executive Engineer (C)
Deendayal Port Authority
OOT - Vadinar

Name of work :- Repairing work of Car Parking Shed & Main gate at Jetty, Vadinar. (R/m of Non residential building & Operational building at Jetty, Vadinar)

Terms & Condition

- 1 The work shall be carried out in accordance with the best workmanship and standard specification to the entire satisfaction of the Engineer-in-Charge.
- 2 All the precaution regarding the safety of workers shall have to be taken by the contractor at his own risk & cost.
- 3 The contractor shall study the local working condition at the site of work before quoting the rate & no claim what so ever shall be entertained.
- 4 All the tools, plants, cranes, ladder etc. and other machinery, storage charges, transportation, insurance, survey fee etc. required for the purpose of execution of work will have to be arranged by the contractor at his own cost.
- 5 Income Tax with surcharges if applicable shall be deducted from the bill as per rules applicable.
- 6 The work should be completed within period of **60 Days** after issuing the work order.
- 7 The contractor or authorized person shall remain present at site during working hours.
- 8 Executive Engineer [Civil] reserves the right to cancel the quotation without assigning any reason and also increase / decrease the quantum the work.
- 9 For the purpose of the measurement the method prescribed in standard code of measurement of concern works shall be applicable.
- 10 The Contractor shall furnish PAN number, GST number & provident fund certificate number along with quotation. Failing which the offer will be liable to discharge.
- 11 Force majeure restricted only to the acts of GOD.
- 12 All the rules and regulations governing DPA will be applicable.
- 13 Document Fee of **Rs.500 /-** [including GST] and EMD of **Rs.4830/-** shall be deposited in Deendayal Port Trust account through NEFT/RTGS, The detail of account as under:

| | |
|------------------------|-----------------------------|
| Name of account | Deendayal Port Trust |
| Name of bank | - Bank of India |
| Branch | - Vadinar |
| IFSC number | - BKID 0003253 |
| Account no | - 325310100002572 |
- 14 EMD in any other form is not acceptable and the offer with other form is liable to rejection.
- 15 In case of Micro and Small Enterprise [MSEs] Valid Govt. Purchase Enlistment Certificate issued by National Small Scale Industries Corporation Ltd., showing list of items related to subject tender and monetary limit must be submitted in order to become eligible for exemption from payment of EMD.
- 16 EMD of the bidders other than L₁ & L₂ will be released within 7 days from the date of opening of the quotation EMD of L₂ will be released on issue of work order to L₁ party and that of L₁ party be released of 1st R.A. bill.

- 17 **Special Condition for GST:** Applicable GST on the taxable value of supply of Goods or Services or both covered in this tender/contract will be paid by Port as reimbursement on production of documentary evidences/reflection of the same under the GSTIN of DPT in GST web portal. Applicable statutory recoveries including TDS under Income tax, TDS under GST acts will be deducted/recovered while accounting for or making payments to the vendor as per the applicable laws.
- 18 If the party is produced wrong PAN no/Invalid PAN no, than as per the income tax rules income will be recovered @ 20%.
- 19 The water & electric connection & electric power will be given at free of cost by DPT but all the arrangement for water/electric supply at site carried out by Contractor at own cost & risk.
- 20 After completion of the work the area should be neatly cleaned by Contractor. No payment shall be given to contractor on this account.
- 21 All material should be got approved by Engineer-in-charge before use and No advance payment shall be given to contractor on this account.
- 22 The quoted rate must be inclusive of all tax and levies (excluding GST) no claims contractor shall be entertained on account of any other taxes levied by central/state government or any authorities paid by him.
- 23 The bidder is complying with all statutory labour laws including Minimum wages Act.
- 24 **Payment Terms:** Payment will be made after completion of work as per terms and conditions and satisfaction of Engineer-in-charge on production of three copies of the bills duly signed sealed by the authorized representatives of the party and verified by Engineer-in-charge. Payment will be made by NEFT/RTGS only in the R.A. bill and final bill.
- 25 The concrete to be used for C.C. & RCC works shall be made of the graded machine crushed trap stone metal and it should be from approved quarry. Mechanical appliances such as concrete mixer, vibrator etc. shall be used for mixing, consolidation etc. of the concrete.
- 26 The working drawing of the proposed works and RCC drawing should be supplied to the contractor during the progress of work as and when found necessary by Engineer-in-charge and decision of Engineer-in-charge Regarding requirement of detailed drawings should be final and bind to The contractor and no claim dispute what-so-ever regarding non-availability of drawings shall be entertained.
- 27 The paints of approved colour and shade shall be made of first quality of Asian paints, I.C.I limited, Nerolac, paints & Putty (acrylic make of JK. Co. Or Asian etc) as approved by Engineer-in-charge.
- 28 For payment purpose the mild steel and TMT bars/MS structural section shall be worked out on the basis of standard cutting length multiplied by standard weight co-efficient as specified in ISI codes. The pins and chairs are not to be paid however same can be considered for the bonafied use. The reinforcement should be cleaned and shall be free for the rust, dust, oil, paints and other foreign matter etc. by the contractor to the satisfaction of engineer-in-charge at his own cost before putting in works. The mild steel and TMT bars shall be make of TATA, JINDAL or equivalent co.

- 29 G.I /MS pipe (medium quality) and all steel structural members (MS angle, MS Plate, MS hollow section etc) fittings shall be Tata, Jindal brand or equivalent with ISI mark as approved by the Engineer-in-charge.
- 30 All RCC works shall be carried out strictly accordance to IS-456-2000 or latest revision.
- 31 The plastering work shall be done with design and grove if required without any extra cost. No dispute shall be entertained on this account at any cost.
- 32 The rates of lying and fixing of G.I. pipeline fixing the clamp and others specials etc. should include cost of additional cutting, cost of jointing or packing materials, nut, bolts etc. If required, no claim on that account will be entertained.
- 33 All the building materials and ingredients of concrete materials such as river sand, coarsed aggregate etc. require for the work shall be got approved from the Engineer-in-charge before stacking at the site of work and the same shall be got tested from Port laboratory at the cost of department, if required, the rejected materials shall be removed immediately from the site of work within 48 hrs. issue of written order otherwise the same will be removed by the department at the cost and responsibility of the contractor.
- 34 **Liquidated Damages/Penalty, if any:**
- (a) In case of delay of contract, liquidated damage [LD] may be levied at the rate of ½% of the contract value per week of delay or part thereof, subject to a maximum of 10% of the contract price.
 - (b) The power if satisfied that the works can be completed by the contractor within a reasonable time after the specified time for completion, may allow further extension of time at its discretion without the levy of L.D. In the event of extension of time at its discretion with L.D. the power will be entitle without prejudice to any other right or remedy available in that behalf per cent [½%] of the contract value of the work for each week or part of the week subject to the ceiling defined in sub-clause.
 - (c) The power, if not satisfied that the works can be completed by the contractor and in the event of failure on the part of contractor to complete work with in further extension of time allowed as aforesaid, shall be entitled, without prejudice to ant other right or remedy available in that behalf to rescind the contract.
 - (d) The power, if not satisfied with the progress of the contract and in the event of failure of the contractor to recoup the delays in the mutually agreed time frame shall be entitled to terminate the contract.
 - (e) In the event of such termination of the contract as described in clauses 36.(i) or 36.(ii) or both the owner shall be entitled to recover L.D. up to ten present [10%] of the contract value and forfeit the security deposit made by the contractor besides getting the work completed by other means at the risk and cost of the contractor.
 - (f) The ceiling of L.D. shall be 10% of the cost of work.

- (g) In case part/portion of the work can be commissioned and part operates the portion for commercial purpose the rate of L.D. will be restricted to the uncompleted value of work, the maximum L.D. being on the entire contract value.
- (h) Note: contract price for L.D. shall be inclusive of tender price plus taxes and duties.
36. Contractor shall procure the cement confirming to relevant Indian Standard of approved Brands like Ultratech, Ambuja, Hathi or equivalent of reputed manufactures holding license to use ISI Certification mark for their product.
37. Supplying & Fixing precoated galvanized iron profile sheets (size, shape and pitch of corrugations approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. and make of Tata, JSW, Stellar, Co. or equivalent (1st quality) for roofing as per requirement.
38. S.S. Main Gate (As per Item no10):
- Providing and fixing of Stainless steel gate as per directed by Engineer in charge make from S.S. (grade 304) Square pipe (hollow section) of Jindal or equivalent co.

Signature of Contractor

Executive Engineer (Civil)
DPA (OOT)Vadinar