

Name of Work: Removal of old Abandoned RCC Jetty structure in between oil Jetty No 2 & 3 at Old Kandla.

Schedule B

Sr.No.	Description	QTY	Unit	Rate	Amount
1	Removal of RCC old jetty above /below G.L. (dismantled concrete shall not be allowed to fall in to sea) including transportation of dismantled material out of port area and lead upto 10 Km , works include Complete removal of Solid piles upto bed level , including bracing beams, columns, slab, slab beam and fixtures and near by existing structures i.e mooring dolphins and other structures by means of cutting RCC structures with diamond cutter machine method, including tools and plants etc. complete removal including disposal of unserviceable materials out of port premises as directed by Engineer-in-Charge.	1.00	JOB WORK		
Total Rs.					

Contractor

Superintending Engineer (PL)
Deendayal Port Authority