


दीनदयाल पोर्ट ट्रस्ट
DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer (TD),
Administrative Office Building,
Post Box No. 50, Gandhidham-Kachchh
www.deendayalport.gov.in

No: TW/WK/7840 / 14/22

Date: 20/10/2022

To,

Expression of Interest.

Name of Work: Construction of D-Type Quarters at Gopalpuri, Gandhidham.

Sir,

Deendayal Port Authority intends to carry out the subject work of TD Division of Civil Engineering Department for a period of 12 months.

Kindly submit your Expression of Interest along with budgetary offer for the items considered in preparation of the estimate under **Annexure-I**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of Interest along with budgetary offer for the above work should reach to the following address on or before 26/10/2022 by 15:00 Hrs.

Address:-

Office of the Executive Engineer (TD),
T.D. Division, Administrative Office Building,
Ground floor, Room No.105, Annexe,
P.O. Box No. 50, Gandhidham – Kachchh.
Email: axencivilkpt@gmail.com

Thanking you,

Yours faithfully,


**Executive Engineer (T.D.)
Deendayal Port Authority**

Annexure-I

BUDGETARY OFFER

Sr. No.	Description of Item	Rate	Unit
			Each
1)	Providing and fixing IS: 12817 marked stainless steel butt hinges with stainless steel screws etc. complete. (Mode of measurement- Each)		
	Aldrops 300x16 mm Size		
	Aldrops 250x16 mm Size		
	Door Latch 250x16x5 mm Size		
	Handle 150 mm		
	Handle 125 mm		
	Handle 100 mm		
	Tower Bolts 200 mm Size		
	Tower Bolts 100 mm Size		
	Floor door stopper		
2)	Providing and fixing M.S. ornamental grills, grilled, doors and gates of M.S. Bars, pipes, GI pipes, M.S. Sheets, flat angles etc. including welding cutting necessary fittings and locking arrangements etc. complete. (Mode of measurement: per KG.)		KG
3)	Providing and fixing glazing in aluminum door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge. Including of aluminum snap beading shall be paid in basic item): (Mode of measurement: per Sqm.)		Sq.mt.
4)	Providing & fixing Netlon Mosquito Net(Insect Screen) as approved by engineer incharge including stitching, fixing all accessories tools, plants, labour and materials etc complete as directed. (Mode of measurement: per Sqm.)		Sq.mt.
5)	Providing and fixing PVC manhole cover Heavy duty with frame 600 x 600 mm size clear opening including cost of all labour & material as directed. Mode of measurement: per Each)		Each
6)	Providing and fixing Stainless Steel towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement complete, as per direction of Engineer in Charge. (Mode of measurement- Each)		Each
7)	Providing and fixing Stainless Steel towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement complete, as per direction of Engineer in Charge. 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88		Each

	mm. (Mode of measurement- Each)		
8)	Dismantling the existing F type bungalow including removing / separating out the salvage materials like doors & windows masonry, reinforcement etc as & where position etc complete including removing the foundation and filling the unwanted material outside Gopalpuri upto 4 km lead, prepare the surface for reconstruction of the bungalow as directed by the Engineer-in-charge (Separate sheet attached). (Mode of measurement: per Sq.mt.)		Sq.mt.
9)	Lettering with black Japan paint of approved brand and manufacture materials complete as directed by the Engineer-in-charge. (Mode of measurement: per letter per cm height)		per letter per cm height
10)	Providing and fixing Aluminium Louvers 500x600 MM in complete as per direction of engineer in charge. (Mode of measurement: per Sq.mt.)		Sq.mt.
11)	providing and fixing mosquito door and Window shutter with aluminium Jali,second class teak wood frame, tower bolt, stopper, handle with stainless steel in complete as per direction of engineer in charge. (Mode of measurement: per Sq.mt.)		Sq.mt.
Total Rupees _____ Only.			