

TD DIVISION

Office of the,
Executive Engineer (TD)
A.O. Building,
Post Box No:50,
G'dham (Kutch)

No:TW/WK/6981 (01)/22-23

Date : / 11 / 2022

To,

_____,
_____,

Name of Work:- Maintenance of main garden and surrounding sweeping work at A.O.Building for Four Months.

Sir

E-quotations are invited for the subject work to be carried out subject to terms and condition attached. Your quotation should reach this office latest by _____ at 15.00 hrs.

SCHEDULE - B

It.N o.	Description of Item	Quantity	Rate	Unit	Amount
1	Disposal of dead body of animals including loading unloading manually or mechanically and disposal the same by tractor /trolley with necessary cover and at appropriate place lead of 4.00 Km including all labour, tools, machinery required complete as directed.	20.00		Each	
2	Cleaning of covered or open S.W.D at A.O.building including culverts by excavating the deposited wet / dry earth, rubbish, garbages etc. lift upto150 cm and stacking & removed the same etc complete upto a lead of 13 km outside the port colony as directed by Engineer-in-charge	424.00		Rmt.	
3	Removal of garbages and waste etc. by tractor / trolley having 4.50 m3 capacity with four labour, tools & plants. Rates inclusive labour, tools & plants, Tractor / trolley, Driver & diesel etc. complete. (as and when required) for lead upto 13 KM from AO Building .	60.00		1 Trip	
4	Upkeeping the area inside A.O.building including open grounds and inside compound wall and with approach by sweeping, collecting and removing, dressing, cutting the grass, jungle weeds, small unwanted trees, plants, babools, vegetation and removal of waste from dust bins. (all the work will be operated together) and disposed off from A.O. Building by tractor / trolley upto 13 km lead or as directed by Engineer-in-charge.	16.00		1 time	
5	Cleaning, washing the U/G and over head tanks of various capacities. The work cosisting cleaning of wall flooring & ceiling by means of spray gun of jet pressure pumps, also removing of all sludge / mud & chlorine deposits accumulated, in water etc. by means of pumping or manually and finally drying by industrial vaccum pump, after cleaning the anti bacterial agents are to be sprayed on all the walls floors & ceiling etc., U.V. radiation in the tank is to be followed to remove infections and flying insects etc. complete. (all labour, materials and tools - tackles)	600.00		KL	
6	Providing Carpenter (First class) & Fitter (Grade-I) for A.O.Building at Gandhidham.	60.00		Day	

It.N o.	Description of Item	Quantity	Rate	Unit	Amount
7	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. (A) Beyond 30 cm girth upto and including 60 cm girth	150.00		Each	
8	Surface dressing of the ground including removing vegetation and in- equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. (A) All kinds of soil	2000.00		M2	
9	Maintenance of main garden at A. O. Building (main garden) island in front of Annexe Bldg. (approx. area 20000 Sq m) flower pots at chairman's wing (approx 30 nos) in A.O. Building including Lawn, Hedges, Ornaments plants and Seasonal Flower, Mehendi Plants, cleaning of walk paths, cutting and giving proper shape to mehendi and other plants and trees. etc. which including keeping surrounding cleaned from un-necessary grass, shrubs, etc. shall be removed regularly and soil made loose periodically and cutting lawns and hedges time to time and healthy development of plants and trees watering, manuring the plants hedges and lawns as per requirement etc. Including hire charges of lawn cutter, tractor with trolley including wages of driver, cleaner complete as directed by engineer-in-charge (excluding the cost of water.)	4.00		Month	
Total Rs.					

Contractor***Executive Engineer (TD)
Deendayal Port Authority***