


# DEENDAYAL PORT AUTHORITY

## Road Division

Office of the Executive Engineer  
(TD)  
Room No. 125, Ground Floor  
ANNEX, Administrative  
Office, Deendayal Port Authority,  
Gandhidham - Kutch  
Pin - 370 201



Mob no. : 08299830390  
Fax : (02836) 220050  
E - Mail : axencivilkpt@gmail.com  
Website :  
www.deendayalport.gov.in

\*\*\*\*\*

TW/WK/7843/

To,

Date 11/03/23

### Expression of Interest

**Sub: Construction of Kendriya Vidyalaya School buildings at Port colony Gopalpuri, Gandhidham**

Sir,

Deendayal Port Authority intends to carry out the subject work of TD Division of Civil Engineering Department for a period of 12 months.

Kindly submit your Expression of interest along with budgetary-offer for the items considered in preparation of the estimate under **Annexure-I**

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of Interest along with budgetary offer for the above work should reach to the following address on or before 18/03/2023 by 15.00 hrs.

**Address :**

Office of the Executive Engineer (TD)  
Town Development Division,  
Annex, A.O. Building,  
Deendayal Port Authority,  
P.O.Box no. 50,  
Gandhidham (Kutch)-370201.  
Email ID : tddivisionkpt@gmail.com  
Thanking you,

Encl. As above

Yours faithfully,

Executive Engineer (TD)  
Deendayal Port Authority

**Budgetary Offer**

Sr. No.	Description of Items	Unit	Rate Rs.
1	Providing and laying auto claved aerated cement blocks masonry with 100 mm thick AAC blocks in superstructure above plinth level upto floor V level in cement mortar 1:4(1cement:4coarsesand).The rate includes providing and placing in position 2 Nos 6mm dia M.S. bars at every third course of masonry work.	Cum	
2	Providing and laying auto claved aerated cement blocks masonry with 150mm/230mm/300mm thick AAC blocks in superstructure above plinth level upto floor V level with RCC band at sill level and lintel level with approved block laying poymer modified adhesive mortar all complete as per direction of Engineer-in-Charge. (The payment of RCC band and reinforcement shall be made for seperately).	Cum	
3	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete :100 MM	Each	
4	Providing and fixing Fiber Glass Reinforced plastic (FRP) Door Frames of cross-section 90 mm x 45 mm having single rebate of 32 mm x 15mm to receive shutter of 30mm thickness. The laminate shall be moulded with fire resistant grade unsaturated polyester resin and chopped mat. Door frame laminate shall be 2mm thick and shall be filled with suitable wooden block in all the three	Rmt.	



Sr. No.	Description of Items	Unit	Rate Rs.
	legs. The frame shall be covered with fiber glass from all sides. M.S. stay shall be provided at the bottom to steady the frame.		
5	Providing and fixing to door frames.  30 mm thick Fiberglass Reinforced Plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF)/Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856, complete as per direction of Engineer-in-charge.	SqM.	
6	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embedding in cement concrete block 30x10x15cm 1:3:6 mix (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size).	Each	
7	Providing and fixing IS:12817 marked stainless steel butt hinges with stainless steel screw etc. complete.	Each	
(i)	Aldrops 300x16 mm Size	Each	
(ii)	Aldrops 250x16 mm Size	Each	
(iii)	Door Latch 250x16x5 mm Size	Each	
(iv)	Handle 150 mm	Each	
(v)	Handle 125 mm	Each	

Sr. No.	Description of Items	Unit	Rate Rs.
vi	Handle 100 mm	Each	
vii	Tower Bolts 200 mm Size	Each	
viii	Tower Bolts 100 mm Size	Each	
ix	Floor door stopper	Each	
8	Providing and fixing chicken wire mesh 150 mm wide 24 gauge with opening of 25x25mm at the junction of RCC or specified, including fixing with GI nails all complete to the satisfaction of the Engineer incharge.	SqM	
9	Providing and applying washable elastomeric paintable putty of approved brand and manufacturer, over following surface to prepare the surface even and smooth, crack free etc. complete of Make Goldenrod innovative solutions	SqM	
3i	Over Fine Sand Plastered Surface		
3ii	Over Coarse Sand Plaster		
10	Applying priming coat with ready mixed rust inhibitive primer for stabilising oxidation and protection gainst corrosion & biological degradtaion, of approved brand and manufacturer, of required shade and colour complete, as per manufacturer's specification	SqM	
4i	One Coat		
4ii	Two Coat		
11	Cutting holes of required size in brick masonry wall for fixing of exhaust fan including providing and fixing 300 mm dia PVC pipe conforming BIS-12818 and making good the same etc. complete as per direction of Engineer-in-charge.  Providing & Fixing of Exhaust fan as per approved brand direction of Engineer-in-charge.	Each	
12	Providing & fixing 10 mm thick multiwall poly carbonate sheet	Sqm	



Sr. No.	Description of Items	Unit	Rate Rs.
	of required shape and shade complete with cost of nuts, bolts, washers, aluminum wind etc. filling of gassheets at joint of sheets and siliearth in joints and gaps. The work also comprises of fixing of aluminum jingles at both sides of sheets as directed by Engineer-in-charge.		
13	Providing and fixing Aluminum Louvers in complete as per direction of engineer in charge.	Sqm	
14	Providing, laying and jointing HDPE Double Wall corrugated (DWC) pipes (excavation to be paid seperately)	Meter	
15	Providing and fixing PVC manhole cover Heavy duty with frame 600 x 600 mm size clear opening including cost of all labour & material as directed.	Each	
16	Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6mm nominal size) as per direction of Engineer-in-charge and finished smooth. Granite Stone of approved shade	sqm	
17	Providing and planting different variety of plants of approved quality and sizes as mentioned including making pits of required size at site, refilled with B.C. Soil mixture manuring and pesticide etc. complete including watering	Sqm	

Sr. No.	Description of Items	Unit	Rate Rs.
	and 90 days maintenance from the date of final bill as per direction of Engineer-in-Charge complete in all respect.		
A	<b>Flowerbed Development (Height 1.5 to 2.5 ft)</b>		
	Varities :- Ixora red, Jetropha Red, Hibiscus, Tecoma, Bougainvillias, Alamanda, Pandanus, Crynum lily, Spider lily, Night queen, Mogra and other etc Including Soil filling, Bed Preparation FYM, spreading, Mixing property Termite treatment, Plants Supply & Planting, Providing bamboo stick support if Weeding, Fertilizer / Pesticide application, Supervision require and Maintaining up to 6 months with mortality replacement approved by Engineer In Charge		
B	<b>Tree Plantation (Height 8 to 10 Ft)</b>		
	Varities :- Neem, Gulmohar, Peltaphorum, Tabubia rosea, Spathodia, Amaltas, Saptparni, Bauhinia, Champa, Including Pit Digging up to 45x45x4 to ,Soil filling, FYM, Mixing property Termite treatment, Plants Supply & Planting, Providing Bamboo Support Weeding, Fertilizer / Pesticide application, Supervision and Maintaining up to 6 months with mortality aproved by Engineer In Chardge		
C	<b>Decorative Palm &amp; Specimen Plants C</b>		
	Varities :- Foxtail Palm, Witchia Palm, Phonix Palm, Nolina Palm, Ficus, Cycas Palm, Bismarkia Palm, Latina Rubra, Triangularis Palm and other etc Including Pit Digging up to 45x45x4 to ,Soil filling, FYM, Mixing property Termite treatment, Plants Supply & Planting Providing Bamboo Support Weeding, Fertilizer / Pesticide		



Sr. No.	Description of Items	Unit	Rate Rs.
	application, Supervision and Maintaining up to 6 months with mortality aproved by Engineer In Chardge		
18	Site Cleaning, Excavation and Waste Desposal	cum	
	Site Cleaning including deberis, civil waste, unwanted vegetation cleaning and Excavation of Soil from 15cm to 60 cm deep and removal of waste up to 500 mtr lead for further garden soil filling approved by Engineer In Charge		
19	Garden Soil Supply	cum	
	Good quality garden soil supply, filling and Primery levelling with jcb / Loder etc for furthe lawn / Flowerbed development approved by Engineer In Charge		
20	Manure Supply	cum	
	Supply of good quality, well rotten cowdung aproved by Engineer In Charge		
21	Supplying of carpet Lawn Including Soil Filling, Soil leveling FYM, spreading, Mixing properly Termite treatment, Semi Carpet grass supply & planting, weeding, watering, Fertilizer / Pesticide application, Supervision, and Maintaining up to 6 months with mortality replacement approved by the Engineer In Charge	Sqm	
23	Extra for using red pigment in top layer of the item of washed stone grit plaster.	Metre	
24	Washed stone grit plaster on exterior walls height upto 10 metre above ground level, in two layers, under layer 12 mm cement plaster 1:4 (1 cement : 4 coarse sand ), furrowing the under layer with scratching tool, applying cement slurry on the under layer @ 2 Kg of cement per square metre, top layer 15 mm cement plaster 1:1/ 2:2 (1cement: 1/2 coarse sand : 2 stone chipping 10 mm nominal size), in panels with groove all around as per approved pattern, including scrubbing and washing the top layer with brushes and water to expose the stone chippings ,complete as per specification and direction of Engineer-in-charge	sqm	
25	Forming groove of uniform size in		

Sr. No.	Description of Items	Unit	Rate Rs.
	the top layer of washed stone grit plaster as per approved pattern using wooden battens, nailed to the under layer, including removal of wooden battens, repair to the edges of panels and finishing the groove complete as per specifications and direction of the Engineer-in-charge :		
(1)	15 mm wide and 15 mm deep groove	meter	
26	Extra for washed grit plaster on exterior walls of height more than 10 m from ground level for every additional height of 3 m or part thereof.	Sqm	
27	Institutional Area Exposed Brick Work, For External Wall with all complete requirement to execute the work , shape & design as approved by Engineer In Charge and as per the direct of Engineer In Charge.	Sqm	
28	Providing and fixing Jet Spray with 2'-6" long PVC pipe With CP brass nut	Each	
29	Providing and fixing partitions for different type of urinals	Each	
(1)	Vitreous white Chinaware Partition Small partitions size 69 x 16.5 x 32.5 cm		