

SCHEDULE-B**Name of work:- "Providing and installation of Block Model of Deendayal Port (Kandla Port)"**

TI No	Description of item	Qty.	RATE	UNIT	AMOUNT
1	Providing Block Model of Kandla Port (Cargo Jetty Area & Oil Jetty Area with surrounding areas) in a desired Scale with best material and requirement. The Model should be placed on best quality iron stand as approved by Engineer-In-Charge. The height of stand should be approx. 0.90m high. The model should be prepared with MDF / Acrylic Block board of required thickness. All the infrastructure facilities like Godowns, storage area, railway lines, Roads, Jetties, storage tanks and other ancillary facilities shall be covered. All the major equipment of Port area shall be covered in the model. The model shall be painted with plastic paint in a desired shade as approved by Engineer-In-Charge. LED lighting is also to be provided as directed of Engineer-In-Charge. Necessary land scaping shall be shown there as per direction of Engineer-In-Charge. All the Transportation and installation is to be done by the Contractor. Before preparing model, the contractor shall give one 3D presentation before Engineer in charge. The model shall cover the area from nakti bridge to satsaida bet and khori creek to 8th oil jetty area as directed by Engineer in charge. Complete model with all the material and labour as directed by of Engineer-In-Charge.	288.00		Sq. ft	

CONTRACTOR

SUPERINTENDING ENGINEER(H)