

SCHEDULE - B

Name of Work:- CSR works for the providing of Solar power system and other facilities for the JEEV SEVA SAMITI at Gandhidham - Providing & laying paver blocks

It. No.	Description of Item	Qty	Rate		Unit		Amount
			In Fig.	In Words	In Fig.	In Words	
1	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	2.70			M3	One cubic meter	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level						
a	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	2.70			M3	One cubic meter	
3	Providing and laying 50mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with Fine sand etc. all complete as per the direction of Engineer-in-charge.	399.47			M2	One square meter	

It. No.	Description of Item	Qty	Rate		Unit		Amount
			In Fig.	In Words	In Fig.	In Words	
4	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge	3.22			M3	One cubic meter	
						Total Rs,	

CONTRACTOR**Executive Engineer (C),
Deendayal Port Authority**