

# **RENOVATION OF ROOM NO. 7 & 8 OF PORT GUEST HOUSE GOPALPURI**

## **Schedule B**

| Sr. No.    | Description in short   | Quantity     | Unit | Rate  |            | Amount |
|------------|--|--------------|------|---|------------|--------|
|            |  |              |      | (In Figure )  | (in Words) |        |
| 1          | Providing and applying gypsum punning up to 4 mm thick to the existing wall surfaces to the proper level & plumb including removing & scrapping of loose painting, filling of cracks & undulations, making required grooves etc complete as directed with all labous and materials.  | 96.00        | M2   |   |            |        |
| 2          | Providing and fixing gypsum false ceilling to the tiolets, PVC-Wooden pattern flooring and wooden penelling to rooms, panelling consisting of 6mm thick ply sheet and 3mm thick superior grade approved veneer including the wooden battens/moulding and melamine polishing etc, floring shall be of superior quality as approved and directed by engineering in chage, complete with all labours etc as directed. | 71.00        | M2   |   |            |        |
| 3          | Renovation of attached toilets of the rooms by removing all the existing plumbing and sanitary fittings pipe lines etc and providing all new fixtures of superior quality as approved including providing an under couter Wash Basin with its Granite Counter, Mirror and its fixtures of approved and supuperior quality quality.   | 2.00         | EACH |   |            |        |
| 4          | Tilling work of the Toilet including removing existing tiles flooring, skirting/dado with its backing flooring/plaster etc and providing new tile floor as well as skirting/dado with its backing as required of approved and superior quality and size/make complete as directed by engeneering incharge with all labours and materials.  | 56.00        | M2   |   |            |        |
| 5          | Finishig the all surfaces with smooth or texture painting to the walls and cielling surfaces and providing Melamine polishing to the wooden surfaces i.e. Wooden pelling, doors frames and shutters etc complete as directed by engineering incharge with all labours and materials.   | 206.00       | M2   |   |            |        |
|            |  | Total Amount |      |   |            |        |
| In Fig.-   |  |              |      |   |            |        |
| In Word-   |  |              |      |   |            |        |
| Contractor |  |              |      | Sd/-<br>Executive Engineer (TD)<br>Deendayal Port Authority |            |        |