


दीनदयाल पत्तन प्राधिकरण  
DEENDAYAL PORT AUTHORITY  
An ISO 9001:2000 Certified Port

(Ministry of Ports, Shipping & Waterways, Govt. of India)

दूरभाष / Tel : 02836 223912  
फैक्स / Fax : 02836 220050  
इ. मेल : tddivisionkpt@gmail.com



अभिशासी अभियंता का कार्यालय (टी.डी.)  
Office of the Executive Engineer (TD)  
उपभवन / Annexe Building  
ए ओ बिल्डिंग पोस्ट बॉक्स न. 50  
A.O. Building, Post Box No 50  
गांधीधाम (कच्छ) / Gandhidham (Kutch)

No: TW/WK/7850/762  
To,

Dated :02-05-2023.

**Expression of Interest**

**Sub: RENOVATION OF ROOM NO. 7 & 8 OF PORT GUEST HOUSE  
GOPALPURI.**

Sir,

Deendayal Port Authority intends to carry out the subject work of T D Division of Civil Engineering Department for a period of 01 Month.

Kindly submit your Expression of interest along with budgetary-offer for the items considered in preparation of the estimate under Annexure-I.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of interest along with budgetary quotation for the above work should reach to the following address on or before 08/05/2023 by 15:00 Hrs.

Address: -

Office of the Executive Engineer (TD),  
Room No 105 Ground Floor Annexe  
Town Development Division, Administrative Office Building,  
P.O. Box No. 50, Gandhidham - Kachchh.

Thanking you,

Yours faithfully,

Sd/-

Executive Engineer (T.D.)  
Deendayal Port Authority



दीनदयाल पत्तन प्राधिकरण  
DEENDAYAL PORT AUTHORITY


An ISO 9001:2000 Certified Port

(Ministry of Ports, Shipping & Waterways, Govt. of India)

दूरभाष / Tel : 02836 223912

फैक्स / Fax : 02836 220050

ई. मेल : tddivisionkpt@gmail.com



अभिशासी अभियंता का कार्यालय (टी.डी)

Office of the Executive Engineer (TD)

उपभवन / Annexe Building

ए ओ बिल्डिंग पोस्ट बॉक्स न. 50

A.O. Building, Post Box No 50

गांधीधाम (कच्छ) / Gandhidham (Kutch)

**Budget Quotation**

**ANNEXURE - I**

Sr. No.	Description	Unit	Rate
1	Providing and applying gypsum punning up to 4 mm thick to the existing wall surfaces to the proper level & plumb including removing & scrapping of loose painting, filling of cracks & undulations, making required grooves etc. complete as directed with all labours and materials.	M2	
2	Providing and fixing gypsum false ceiling to the toilets, PVC-Wooden pattern flooring and wooden paneling to rooms, paneling consisting of 6mm thick ply sheet and 3mm thick superior grade approved veneer including the wooden battens/molding and melamine polishing etc., flooring shall be of superior quality as approved and directed by engineering in charge, complete with all labours etc. as directed.	M2	
3	Renovation of attached toilets of the rooms by removing all the existing plumbing and sanitary fittings pipe lines etc. and providing all new fixtures of superior quality as approved including providing an under coulter Wash Basin with its Granite Counter, Mirror and its fixtures of approved and superior quality quality	Each	
4	Tilling work of the Toilet including removing existing tiles flooring, skirting/dado with its backing flooring/plaster etc. and providing new tile floor as well as skirting/dado with its backing as required of approved and superior quality and size/make complete as directed by engineering in charge with all labours and materials.	M2	
5	Finishing the all surfaces with smooth or texture painting to the walls and ceiling surfaces and providing Melamine polishing to the wooden surfaces i.e. Wooden pelling, doors frames and shutters etc complete as directed by engineering in charge with all labours and materials.	M2	
TOTAL Rs.			