


दीनदयाल पत्तन प्राधिकरण  
DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer (TD),  
TD Division,  
Administrative Office Building  
Post Box No. 50, Gandhidham-Kachchh  
[www.deendayalport.gov.in](http://www.deendayalport.gov.in)

\*\*\*\*\*

No: TW/WK/7855/

Date:- 02/05/2023

To,

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Expression of Interest.**

**Sub:- Painting work to DPA Guest House at Ahmedabad.**

Sir,

Deendayal Port Authority intends to carry out the subject work of TD Division of Civil Engineering Department.

Kindly submit your Expression of Interest along with budgetary – offer for the items considered in preparation of the estimate under Annexure-I.

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your expression of interest along with budgetary quotation for the above work should reach to the following address on or before **08/05/2023 by 15:00 Hrs.**

**Address:-**

Office of the Executive Engineer (TD),  
TD Division, Administrative Office Building,  
Room No. 105, Ground floor, Annexe,  
P.O. Box No. 50, Gandhidham – Kachchh.

Thanking you,

Yours faithfully,

  
**Executive Engineer (TD)**  
**Deendayal Port Authority**



**TD DIVISION****BUDGETARY OFFER**

Sr. No.	Description	Qty.	Unit	Rate	Amount
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	850.00	M2		
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	850.00	M2		
3	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: (A) Two coats on old work.	850.00	M2		
4	Finishing walls with Acrylic Smooth exterior paint of required shade : (A) Old work (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	900.00	M2		
5	Painting two coats (excluding priming coat) on previously painted steel and other metal surfaces with ENAMEL PAINT. Brushing interior to give an even shade including cleaning the surfaces of all dirt, dust, and other foreign mater onsurfaces over 10cm in width / girth.	100.00	M2		
6	Providing and fixing brass bib cock of approved quality : (A) 15 mm nominal bore	8.00	Each		
7	Providing and fixing sets of Bathroom Accessories of reputed brand and matching designs with concealed/ hidden screws strictly upon approval by engineer-in-charge. The cost shall include proper and careful fixing of all sets with Galvanised countersunk screws and nylon gattis as required without damaging existing pipelines, conduits, cables, wires, switchboards or any such item concealed inside wall below the tiles. The fixing must be in proper level and at places as directed by the engineer-in- charge (A) 32 mm dia Waste pipe	5.00	Each		
	(B) PVC Connector to Wash Basin( 0.60 m)	5.00	Each		

	(C) C.P.Brass Waste Coupling of wash basin	5.00	Each		
8	Painting of wall texture as per selection with complete material & labour as directed by Engineer in charge.	35.00	M2		