

Page 1
SCHEDULE - B

Name Of Work:-Dismantling of P & C building at New Kandla.

Item No.	Description of item	Qty	RATE		UNIT		AMOUNT
			In Figures	In Words	In Figures	In Words	
1	Demolition of framed structure building including its all offices, rooms, toilets, stores, stairs, from ground level / plinth level to up to floor three level (i.e. G+2 storey building) with RCC columns, beams, slabs, chajjas, lintels, plinth beams, projections, balcony etc. from building including block/stone masonry etc. and disposal of debris having lead of apprx. 5.00 km. The complete demolition and disposal including loading, unloading and transporting shall be done by mechanical means i.e. by using JCB, Pay loaders, Dumpers Dozers, etc. or as directed by Engineer in charge. Nothing will be paid for dismantling/demolition and disposal of the said structure. The material like usable C.C. blocks received from the Buildings will be the Property of Contractor against demolition of the above said structure. The debris received after demolition shall be disposed off and dressed at the site within 5.00 Km lead as directed by Engineer In Charge. The contractor has to quote the rates for taking away all the steel scrap material (includes reinforcement & structural steel), wooden scrap material and aluminum scrap material obtained from the dismantling/demolition of the said structure after deducting/considering the cost of demolition of the structure.						
i)	Steel Scrap Material	44000.00			Kg		
ii)	Taking away all the wooden scrap material	139.00			Sq.m		
iii)	Taking away all the Alluminium scrap material	1600.00			Kg		

Contractor

Executive Engineer (Harbour)
Deendayal Port Authority