

दीनदयाल पत्तन प्राधिकरण  
DEENDAYAL PORT AUTHORITY



Office of the Superintending Engineer (PL),  
Pipeline Division,  
Administrative Office Building  
Post Box No. 50, Gandhidham-Kachchh  
Email: seplkpt@gmail.com  
www.deendayalport.gov.in

\*\*\*\*\*

No: CN/WK/1654/Ghogha Portable Ramp/169

Date: 14/07/2023

To,

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Expression of Interest**

**Sub: - Request for EOI for "Execution of Portable Ramp on Pontoon at Ghogha Terminal-" - Reg.**

Sir,

Deendayal Port Authority intends to carry out the work for "Execution of Portable Ramp on Pontoon at Ghogha Terminal".

Kindly submit your Expression of Interest along with a budgetary – offer as per the prescribed format i.e. Annexure-I.

The rates quoted must be inclusive of all taxes, duties for performing the scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your expression of interest along with a budgetary quotation for the above work should reach the following address on or before **21/07/2023 by 15:00 Hrs.**

**Address: -**

Office of the Superintending Engineer (P),  
Project Division, Administrative Office Building,  
Room No. 221, First floor, Annexe,  
P.O. Box No. 50, Gandhidham – Kachchh.

Thanking you,

Yours faithfully,

Superintending Engineer (P)  
Deendayal Port Authority



**PROJECT DIVISION****BUDGETARY OFFER**

<b>Sr. No.</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate</b>
1	Supply, fabricate, transport, handle and erect in proposed ramp structure made of Structural steel tubular members of any diameter conforming to API 5L Grade B or its equivalent and/or Structural steel shapes, plates, anchor bolts and built up sections conforming to IS 2062 Grade BR-E250 including profile cutting, assembling, hoisting, fixing in position, welding, inspection and applying a priming coat of approved steel primer and top coat of minimum thickness as specified in the specifications made of approved paint all as per specifications and drawings including cost of all materials, fitting charges, all labour charges, transportation charges and minor tools etc. complete. The cost shall include all fabrication, transportation of the steel structure assembly in part or as a whole, lifting using floating crafts and cranes, erection and fixing on the pontoon with appropriate supporting arrangement, base plates and anchor bolts etc. complete.	27.00	MT	
2	Dismantling of Structural steel members of any dimension, steel pins made of alloy steel castings and shapes, plates, anchor bolts and built up sections conforming to specifications including profile cutting, assembling, hoisting, fixing in position, welding, inspection and as per drawings including cost of all materials, fitting charges, all labour charges, transportation charges and minor tools etc. the work also comprises of taking away all the dismantling material with stacking, loading and unloading with all machineries, equipments and labours etc. complete as directed by Engineer in charge.	19.00	MT	

3	Providing and placing in-situ cement concrete of grade M30 for concrete grout of 175 mm thickness (average) concrete over the pontoon deck, all as per drawings with necessary gradient, shuttering, mixing, curing & bonding agent wherever required, transporting, placing, vibrating, finishing and curing the concrete including all labour, materials, tools, equipment, fuel and all sampling, testing and records etc., complete. Rates includes curing & bonding coat agents.	1.00	Cum	
---	---	------	-----	--