

**PROJECT DIVISION**



Office of the Executive Engineer  
(TD), Administrative Office Building  
Post Box No. 50, Gandhidham-  
Kachchh  
www.deendayalport.gov.in

NoCN/WK/1600( ) / 22-23 /

Date : / / 2023

To,

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Name of Work** : - "Providing and fixing water cooler at Ro Pax Terminal Hazira."

Sir

Sealed quotations are invited for the subject work to be carried out subject to terms and condition attached. Your quotation should reach this office latest by \_\_\_\_\_ at 15.00 hrs.

**SCHEDULE - B**

Sr. No.	Description	Qty	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing and fixing of water cooler of capacity of 150 litres with installation of sintex or equivalent water tank over Terrace of 1000-liter capacity with all necessary pipes, fitting, tools and plant as directed by engineer-in-charge at ROPAX Terminal Hazira Surat.	3			Each	
2	Providing and fixing pre coated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per Sqm as per IS :277, in 240 mpa steel grade, 5-7 microns' epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self-drilling/self-tapping screws complete: Ridges plain (500-600 mm)	105.00			Mtr	
3	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	409.43			Kgs	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centring and Shuttering-All work up to plinth level: 1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size).	6.00			cum	

Quotationer

Superintending Engineer (P)  
Deendayal Port Authority