

## DEENDAYAL PORT AUTHORITY

**Sub :- CSR Work - Providing water supply pipeline for drinking water facilities for poor people and fisherman at Vandi Village.**

### SCHEDULE-B

Sr. No.	Description of Items	Total Qty.	Rate	Unit	Amount
1	Providing and fixing Chlorinated Polyvinyl Chloride(CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.				
i)	75 mm nominal inner dia Pipes	1315.00		Metre	
2	Providing and fixing gun metal non- return valve of approved quality (screwed end) :				
i)	80 mm nominal bore, Horizontal	8.00		Each	
3	providing and fixing of mono block centrifugal pump having ISI mark 5.5 kw/7.5 Hp with outlet size 75x65 mm including necessary fittings i.e in let ,out let pipes and elesticty connection as directed by Engineer in charge	1.00		Each	
4	Constructing masonry Chamber 60x60x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box 100mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size ) , i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design :				
a	With common burnt clay F.P.S.(non modular) bricks of class designation 7.5	8.00		Each	
<b>Total Rs.</b>					