

Name of work:- Providing Paver Block paving in Port dispensary at Adipur (R/m of Non-Residential building at Gopalpuri)

Schedule B

Sr. No.	Description in short	Quantity	Unit	Rate		Amount
				(In Figure)	(in Words)	
1	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	718.08	M2			
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	90.00	M2			
		Total Amount				
In Fig.-						
In Word-						
Contractor				Executive Engineer (TD) Deendayal Port Authority		