


Bill Of Quantity


Name of Work: Supplying & Installation of RO plant, Water cooler and Water Tank at Ghogha Terminal

Sr. No.	Description of Items	Quantity	Rate		Unit		Amount
			In Fig.	In Words	In Fig.	In Words	
1	Supply and installation of RO plant of Capacity 250 LPH with Water Cooler of 150 liter storage capacity and 3 Nos. of taps. The work includes providing and fixing of power stabilizer with necessary arrangements for suitable electricity supply with necessary arrangements for suitable electricity supply such as wiring, plug point etc. complete. The work comprises of supply and installation of Two Nos. of Kaka eON 3 layers ISO standard water tank of 1000 liters capacity upto 5.00m height and inclusive of all necessary ISO standard fixtures and fittings (i.e. Valves, bends, tees, pipelines, and any other required materials as per site condition) required for smooth functioning of RO plant and water cooler. The work also comprises of to provide one year warranty and service for the RO plant and cooler with all labours and materials at free of cost. The whole job work is carried out as directed by Engineer in charge with all materials, labours, tools and tackles etc. complete	1.00			Job Work	Job Work	
Total = Rs.							

Note: The rates should be inclusive of all taxes, duties, fees, cess etc. and all incidental charges but exclusive GST.

CONTRACTOR


Superintending Engineer (PL)
Deendayal Port Authority



29