

**Construction - 1 Division**

**Name of Work:- Excavation/Cutting in Water Front Area at Roll-on/Roll-off (Ro-Ro) facilities for Handling of ODC Cargo at Bunder Basin, Kandla.**

**Bill Of Quantity**

Item No.	Description	QTY	RATE		UNIT		AMOUNT
			In Fig.	In Words	In Fig.	In Words	
1	Excavate & get out in foundation & Trenches in wet soil or below sub soil water level, Dressing the bottam to the required level & plumbing the sides as per the dimentions & banking and depositing excavated stuff upto 5 km including dewatering etc. complete as directed.	8000.00			cum	one cubic meter	
						Total :-	

**Contractor****Executive Engineer(C-I)  
Deendayal Port Authority**