



Office of Executive Engineer (Electrical), Ground Floor, Nirman Bhavan, New Kandla, Kutch, Pin Code 370210. Email: xenedpa@qmail.com

No.: EL/WK/2847 Date:13/08/2024

CORRIGENDUM

Subject: "Supply, Installation, Erection, Testing and Commissioning of 66KV metering CT's and PT's along with SITC of GETCO approved ABT Meters at 66KV IOCL Receiving Yard at Kandla."

With reference to above, the corrigendum is issued with revised Work(BOQ), The bidder may quote their rates as mention below:

Name of work: - REPLACEMENT OF 66KV METERING CT`S/PT`S AND SITC 2 NOS. ABT METERS AT IOCL YARD KANDLA

| Sr. No. | Description | Unit | Qty | Supply Rate | Amount | Installation, Testing, Commissioning | Amount |
|---------|--|------|------|----------------|--------|--|--------|
| 1 | Supplying, Installation, Testing and Commissioning incl. replacement of 66 kV Outdoor Live/Dead tank, oil filled, Oil filled 0.2s metering Current Transformer with 60/1 as per GETCO specifications including loading/unloading, receiving from stores, testing & commissioning along with replacement of existing CT's | No. | 3.00 | | | | |
| 2 | Supplying, Installation, Testing and Commissioning incl. replacement of 66 kV Outdoor Live/Dead tank, oil filled,0.2 metering Potential Transformer as per GETCO specifications including loading/unloading, receiving from stores, testing & | No. | 3.00 | | | | |

| | commissioning along with replacement of existing PT`s | | | | | |
|---|--|------|-----|--|--|--|
| 3 | Supply, Installation, Testing, Commissioning of Armoured Control Cable of 4CX4sqmm copper as per site requirements along with its termination | Mtr. | 100 | | | |
| 4 | Supply, Installation, Testing, Commissioning of Aluminium Clamps, Connectors & Conductors complete with all tools & tackles, Labours & Materials | No. | 12 | | | |
| 5 | Supply, Installation, testing and Commissioning of ABT Meters as per GETCO Approved specifications of 0.2S accuracy class with GSM Modem and ABT Meter Panel with GETCO Liasoning, Duly tested at NABL lab and approved by GETCO including all accessories required to complete this job | No. | 2 | | | |
| 6 | Testing of 66KV Metering CT, Metering PT and ABT Meter as per GETCO Norms | Job | Job | | | |
| | | | | | | |
| | | | | | | |

-sd/

Signature & Seal of Contractor

Executive Engineer (E) Deendayal Port Authority