

DEENDAYAL PORT AUTHORITY
OFF SHORE OIL TERMINAL VADIANR

SUB: R/M of non residential building port colony, Vadinar.

N/W :- providing and laying paver block flooring in school at port colony

SCHEDULE - B

ITEM no	Description	qty	rate	Unit	Amount
1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge: All kinds of soil.	290	74.9	M2	21721.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size	29	4783.38	M3	138718.02
3	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	290	665.7	M2	193053.00
					353492.02
			total Rs.		353492

I/We am/are agree to execute the above work,

at _____% above (In figure), _____% above(In words)

at _____% below (In figure), _____% below(In words)

Sign of Contractor

Executive engineer (C)
Deendayal Port Authority- OOT
Vadinar

