

Name of work: - S/R to Sports Complex at Port Colony Gopalpuri, Gandhidham.

Schedule - B

Item No.	DESCRIPTION	Qty.	RATE (In ₹.)		Unit		AMOUNT (In ₹)
			In Figure	In word	In Figure	In word	
	PART -A Execution						
1	Football Ground						
(i)	Refurbishment of the base etc. for Installation of synthetic artificial turf for a football field from a FIFA preferred provider as per tender.	9690.00			M2	One square meter	
(ii)	Supply and Installation of synthetic artificial turf for a football field from a FIFA preferred provider having finger unit coating permeable backing, pile height 50mm, polyethylene slit filament, fire retardant, certified lead free, including customs clearance, insurance, infill comprising of rubber (0.85 kg/sft) and silica sand (2.4kg/sft). The proposed brand needs to be from America/Europe/Australia origin only. The agency also needs to provide unloading and staging of rolls, sewing of seams, infilling with appropriate dispensing, spreading and levelling equipment, brushing of fibres with all poly-hydraulic controlled equipment as directed by Engineer in charge.	9690.00			M2	One square meter	

2	Athletic Track						
(i)	Refurbishment of the base etc. for Installation of synthetic athletic track all complete as per requirements/specifications laid down by World Athletics (IAAF) preferred provider including UV Seal Coating.	3200.00			M2	One squire meter	
(ii)	Supply and Installation of synthetic athletic track including markings on the surface all complete as per requirements/specifications laid down by World Athletics (IAAF) from a firm who had previously supplied and installed the original cast in-situ athletic track.	3200.00			M2	One squire meter	
3	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement : 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement : 6 fine sand).	299.10			M2	One squire meter	
4	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	10000.00			kg	One Kg	
5	Providing and laying of interlocking C.C. paver block (80 mm thick, M-30) as per site requirement all complete as directed by Engineer-in Charge.	714.12			M2	One squire meter	
6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete : 250 mm dia. R.C.C. pipe	80.00			M	One meter	
7	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge: (A) All kinds of soil	24.00			M2	One squire meter	

8	Constructing brick masonry road gully chamber 50x45x60 cm with bricks in cement mortar 1:4 (1 cement : 4 coarse sand) including 500x450 mm pre-cast R.C.C. horizontal grating with frame complete as per standard design : With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	4.00			Each	Each	
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	10.00			cum	One cubic meter	
10	Providing and fixing of 3 Seater Public Place Seating Chair of Aluminium with arm and backrest WITHOUT CUSHION as approved by Engineer-in Charge.	10.00			Each	Each	
11	Supply, Installation and Fixing of UDDS 5500 Nits Brightness, Outdoor Mild Steel Led Display System including all accessories complete as directed by Engineer-in Charge.	1.00			Each	Each	
12	Supply and fixing of UV stabilised 2 mm thick corrugated FRP sheet for 3 Seater Chair Roof, all complete as per direction of Engineer-In-Charge.	90.00			M2	One square meter	
13	Providing of manure (goat dropping & cow dung dried) free from foreign materials subject to the approval of Engineer in charge including loading, unloading, transport.	10.00			M3	One cubic meter	
14	Providing of sweet earth including cost of excavation, royalty loading, unloading, transport & stacking in site of work.	80.00			M3	One cubic meter	
15	Providing of decorative / ornamental plants of various types and sizes as directed by engineer-in-charge.	200.00			No.	One Number	
						Total	
	(Rs. In word_____)						
	CONTRACTOR						Executive Engineer (TD), Deendayal Port Authority

	PART - B Credit item pay to DPA						
1	Removal of existing football turf, Surface dressing of the ground including removing and disposal of same & transportation. The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as directed by Engineer in charge.	9690.00			M2	One squire meter	
2	Removal of existing synthetic athletic track, Surface dressing including removing and disposal of same & transportation at local body location approved. The operation shall be carried out after scrapping and properly cleaning the surface to remove loose particles with wire brushes, complete in all respect as directed by Engineer in charge.	3200.00			M2	One squire meter	
						Total	
	(Rs. In word _____)						
	CONTRACTOR						Executive Engineer (TD), Deendayal Port Authority