



DEENDAYAL PORT Authority

(Formerly known as Kandla Port Authority)

Office of the Superintending Engineer,
3rd Floor, Nirman Building,
New Kandla (Kutch), Gujarat-370210.



Tel: (02836)270209 / 270342
FAX: (02836) 270184 /270475



No.EL/WK/2872

Date: 26 /02/2025

To

M/s. _____,

Subject – “Offer for Supply of material & Solid Tyres execution work for 63 T HMCs.”

Sir,

Deendayal Port Authority intend to execute the work of solid tyres & supply of material the enclosed (Annexure-A) for the use of Mobile Harbour Cranes.

The offer along with (Annexure-A) hard copy should reach this office of undersigned on or before 10/03/2025 at 14.30 hrs. or scanned copy of scanned offer also accepted on e-mail see@deendayalport.gov.in/csdkandla@gmail.com which shall be opened on the same day.

Therefore, it is requested to send your details offer along with all terms and conditions at the earliest.

Encl: As above

Yours faithfully,

S/d-
Superintending Engineer (E)
Deendayal Port Authority.

Annexure-A

Subject – “Offer for Supply of material & Solid Tyres execution work for 63 T HMCs.”

SR. No.	Description	Unit	Qty.	Rate/per unit.	Amount
1	Fixing Solid off-road type tyres Natural Rubber Load bearing Capacity 9000 kilogram @ 20 Kms. As per technical specification No.1	Nos.	32		
2	Supply of HUB fabricate & wheel HUB as per the original for 63THMCs	Nos.	02		

Signature & Seal
Of Contractor

S/d-
Superintending Engineer (E)
Deendayal Port Authority

SCOPE OF WORK

1. General:

Deendayal Port Authority intends to the following fixing Solid tyres for 63T HMCs cranes.

1. Technical Specification for Item No.1

This include fixing of following type Solid tyres. This including fixing of all required materials. The fixing shall be made in such a way that the fixing shall be mechanically permanent. The work by validated person will be carried out includes all labour, tools tackles, fixing of as directed by Engineer-in-Charge. The contractor will have to pay a penalty in case of any damage to the material during the work. The Rim and Tyre shall be collected from site at inside cargo jetty area and after fixing same shall deposit.

Solid off-road Tyres each with the following feature	
Load bearing Capacity	9000 kilogram @ 20 Kms.
SIZE in (inch)	14.00 x 24
Type of assembly	Only solid wheel without rim
Construction	Natural Rubber
Rim Width (Inch)	10.00
Pattern	LUG
Dimension	1278OD, 345SW

2. Technical Specification for Item No.2

This include Supply of HUB fabricate & wheel HUB as per the original for 63T capacity Mobile Harbor Crane at Kandla. Before supply the material, contractor shall be visit the site and ensure the size and materials to suitable as per original for the said cranes.

Signature & Seal
of Contractor

S/d-
Superintending Engineer (E)
Deendayal Port Authority

Terms & Conditions

1. The contract shall be effective 2 months from the issue of work order. The work shall be initially completed for 16 tyres within 03 days after collect the material from site. Also, remaining 16 Nos. tyres within 03 days as directed by Engineer-In-charge.
2. The rates quoted must be inclusive of all taxes and levies (Excluding GST), No claims of contractor shall be entertained on account of any other taxes levied by central / state government or any authorities paid by him.
3. The contractor shall study the local working conditions at the site of work before tendering and no claim what so ever shall be entertained.
4. The work shall be carried out in accordance with the best standards of workmanship and to the entire satisfaction of the Engineer-in-Charge.
5. 1st & Final Bill shall be paid after satisfactory completion of the work.
6. CME reserves the right to cancel the quotation without assigning any reasons and increase/decrease the quantum of work.
7. All tools, plants, scaffolding ladder etc. and other machinery etc. required temporary for the purpose of execution of work will have to be arranged by the contractor at his own cost and storing of such tools, plants etc. will have to be made by him.
8. All the materials should be got approved from Engineer-in-Charge before put into use.
9. TDS ON GST:
TDS provision under GST Acts, 2017 are in force from 01.10.2018 and accordingly TDS under GST Act will be deducted @ 2 % (1% CGST and 1 % SGST or 2 % IGST) from payment / credit give to contractor / contract / professional and other for work order / contract exceeding Rs. 2,50,000/-.
10. Deduction of Income-Tax and GST:
Income-Tax deductions and surcharge and GST+TDS provision under GST Act as applicable thereon shall be made good while making payments due to the contractor for carrying out the work and only net amount shall be paid as directed by the Central Board of Direct Taxes, Ministry of Finance, Government of India.
11. The contractor has to arrange Gate Passes for entry/exit of labours and

equipment's / vehicles inside/outside Cargo Jetty area at his own cost from CISF.

12. All the rules & regulations governing DPA will be applicable.
13. The Contractor shall ensure not to cause any damage to the port properties in the vicinity of work site during execution of work. If any damage occurs due to workmen/machinery of the contractor, the contractor has to make good the loss/damage at his cost.
14. In respect of delay in completion of work beyond 30 days, Liquidated Damages (LD) @ ½% of the contract value per week and part thereof will be levied subject to maximum of 10% of contract value. However, if the delay is attributable to DPA, extension for completion of work will be granted without levy of LD.
15. Taxes & Duties: GST Extra @ 18% Income Tax & GST will be deducted at applicable rates.
16. Travel, accommodation & local conveyance: Inclusive in the rate quoted above.

Signature & Seal
of Contractor

Sd/-
Superintending Engineer (E)
Deendayal Port Authority