


दीनदयाल पत्तन प्राधिकरण
DEENDAYAL PORT AUTHORITY
An ISO9001:2000 Certified Port
(Ministry of Ports, Shipping & Waterways, Govt. of India)

दूरभाष / Tel : 02836 223912
फैक्स / Fax : 02836 220050
ई. मेल : tddivisionkpt@gmail.com



अभिशासी अभियंता का कार्यालय (T.D)
Office of the Executive Engineer (T.D)
उपभवन / Annexe Building
ए ओ बिल्डिंग पोस्ट बॉक्स नं. 50
A.O. Building, Post Box No.50

No: TW/WK/7840-I/1938

Dated: 18/03/2025.

To,

.....
.....
.....
.....

Expression of Interest

Sub: Construction of E & D type quarters at Gopalpuri (Stage-I "D" type).

Sir,

Deendayal Port Authority intends to carry out the subject work of TD Division of Civil Engineering Department.

Kindly submit your Expression of Interest along with budgetary offer for the items considered in preparation of the estimate under Annexure-I

The rates quoted must be inclusive of all taxes, duties for performing scope of work and exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your expression of interest along with budgetary quotation for the above work should reach to the following address on or before 25/03/25 by 1500 hours.

Thanking you,

Address :

Office of the
Executive Engineer (TD)
Administrative Office Building,
Ground Floor, Annexe, Room No. 103,
Post Box No. 50,
Gandhidham - Kutch

Yours faithfully,


Executive Engineer (TD)
Deendayal Port Authority

Annexure - I

Name of work : Construction of E & D type quarters at Gopalpuri (Stage-I "E" type)

Sr.No.	Description of item	Unit	Quantity	Rate	Amount
1	Collection of Sweet Earth including cost of excavation,royalty,loading,unloading,transport and stacking at site of work.	M3	1361.6		
2	Collection of manure(goat dropping and cow dung dried) free from foreign materials,subject to the approval of engineer of charge including cost of excavation,loading,unloading,transport and stacking at site of work.	M3	137		
3	Supplying decorative/ornamental plants of flower/show plant of height 3 to 5 feet various types as directed by engineer in charge	Nos	500		
4	Finishing Wall with 2 to 3 mm thick texture paint including cleaning surface and applying one coat of cement primer including all material and labour complete as directed by engineer in charge	M2	200		
5	Providing and laying non-pressure NP3 class 300 mm dia R.C.C. pipes laid under sand/stone dust bed of 50 mm,jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including excavation,refilling and testing of joints etc complete.	Rmt	320		
6	Providing and fixing PVC modular kitchen cabinet shutters of 19 mm comprising of PVC framing with pipe of 38 mm x 25 mm, PVC Plain/Offset Patti as per requirement, bonding with Cyanoacrylate Adhesive and Hinges of 100 x 25 x 3 mm,screwing with 60 x6 mm and PVC handles of 100 mm complete as directed by engineer in charge.Variation in profile dimension in higher side shall be accepted but no extra payment on this account shall be made.	M2	82		