




## DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer,  
Harbour Division, Nirman Building  
New Kandla (Kutch)  
Gujarat-370210

Tel : (02836) 270325  
FAX : (02836) 270429  
Email ID : kphdivision@gmail.com

ISO 9001:2008 ISO 14001:2004

No. HW/WK/EOI

Date: 29.04.2025

To,  
M/s

### **Expression of interest**

Sub: Dismantling of existing godown no.18 & 24 inside cargo jetty area.

Sir,

Deendayal Port Trust intends to invite e-tender for the subject work. Kindly submit your Expression of interest along with budgetary-offer for the subject work on the basis of tentative requirements of material enclosed herewith. The rates quoted must be inclusive of all taxes, & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes. Your Expression of interest along with budgetary offer for the above work should reach to the above mentioned address on or before **08/05/2025**.

Thanking you,  
Encl. As above

Yours faithfully

Executive Engineer (H)  
Deendayal Port Authority

To  
The Executive Engineer (H)  
Deendayal Port Authority,  
New Kandla (Kutch)  
Gujarat-370201

Sub: Budgetory offer for the various civil items & credit items for the work "**Dismantling of existing godown no.18 & 24 inside cargo jetty area**".

Sr. No.	Description of Item	Qty	Rate	Unit	Amount
	<b>Part-'A' (Dismantling Work)</b>				
<b>1</b>	Dismantling/ demolishing of existing Godowns above floor level inside cargo jetty area. The godowns were constructed with RCC frame structure and C.C.block masonry. The works includes removal of reinforcement from RCC structure, dismantling of A.C.sheet roof and RCC/ Structural steel trusses, purlins, wind bracing, wind ties, gates etc. After dismantling the scrape materials like A.C. sheet, structural steel, steel reinforcement etc. will be stack at the site of work properly and to be taken away by the contractor on as is where is basis after depositing the amount quoted under credit item. The debries obtained from the dismantling the godowns will be disposed-off up to the lead of 2 km outside cargo jetty area and spreading at the disposal site as directed by engineer-in-charge. The area to be measured out to out of wall for payment purpose.	<b>13348.00</b>		<b>M2</b>	
	<b>Part 'B' (Credit Item)</b>				
<b>1</b>	Taking away of dismantled material like A.C. sheets, Steel reinforcement bars, Structural steel etc. obtained from the item no. 1 of Part-'A' as and where basis including loading/unloading transporting, cutting in peices ifrequired etc. complete and clear the site as directed by Engineer in charge. The rates exclusive of GST.				
<b>A)</b>	A.C sheets	<b>7341.00</b>		<b>M2</b>	
<b>B)</b>	Steel reinforcement bars.	<b>40044.00</b>		<b>Kg</b>	
<b>C)</b>	Structural steel	<b>133480.00</b>		<b>Kg</b>	

**Note : Rates shall be exclusive of GST**