

DEENDAYAL PORT AUTHORITY



SIPC
KANDLA
RIDE THE WAVE OF PROGRESS



Office of the Executive Engineer(Construction),
Room No. 114, Ground Floor,
ANNEX, Administrative Office
Gandhidham – Kutch, Pin – 370 201
E – Mail: - executiveengineercivil1@gmail.com

No.CN/WK/CSR/

Dated: 13/05/2025

To,
M/s _____

Expression of Interest

Sub: Budgetary-offer for Dismantling of existing Structural shed & Erection of same at new location at Shri Antarjal Panchayat Prathmik Group Shala.

Sir,

Deendayal Port Authority intends to carry out the subjected work under CSR initiative as per the Scope of work, Technical specification, Terms &, Conditions stipulated below.

Kindly submit your Expression of interest along with budgetary-offer in the format given in **Annexure-I.**

The rates quoted must be inclusive of all taxes, duties for performing scope of work & exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of interest along with budgetary offer for the above work should be submitted through email to the id: executiveengineercivil1@gmail.com or hard copy to the following address on or before **20/05/2025 by 16:00 Hrs.**

Office of the Executive Engineer(Construction),
Room No. 114, Ground Floor,
ANNEX, Administrative Office Gandhidham,
Dist. Kutch, Gujarat, Pin – 370 201
E – Mail: executiveengineercivil1@gmail.com

Thanking you,

Executive Engineer (Construction)
Deendayal Port Authority

Annexure-I

BUDGETARY OFFER FORM

To:
The Executive Engineer (Construction),
Deendayal Port Authority (DPA),

Sub: Budgetary-offer for Dismantling of existing Structural shed & Erection of same at new location at Shri Antarjal Panchayat Prathmik Group Shala.

Dear Sir,

The budgetary offer for the subject work in accordance with your EOI request letter 28/01/2025 is given as under.

It.No.	Description of Item	Unit	Rate
1.	<p>"Part A"</p> <p>Dismantling of existing structure shed of approximately 12m x 15m to recover whole truss, column, GS roofing sheet, ridges, hips, valleys and gutters and demolition of civil Foundation structure upto 0.5m below ground including RCC columns, Plinth beams, slabs/floor, cutting & removal of steel bars, Earth etc. and disposal of debris having lead up to 3.00 km (if directed). The complete demolition and disposal including loading, unloading and transporting shall be done by mechanical means i.e. by using JCB, Pay loaders, Dumpers Dozers, etc. or as directed by Engineer in charge. The material like electric fittings, wires etc. received from the Structure will be the Property of Client.</p> <p>"Part B"</p> <p>Erection of the structural shed above plinth level using recovered material from dismantling, including hoisting, fixing in position, and welding to complete the work. This includes providing and fixing foundation bolts, re-fixing the dismantled roofing sheet, ridges, hips, valleys and gutters and providing and fixing J or L hooks, bolts, nuts, and washers.</p>	Lum Sum	

Note: The budgetary offer is inclusive of all taxes, duties for performing the work & exclusive of GST.

Signature [In full and initials]:

Name & Title of Signatory:

Name of Agency: