



# Tender Details

Tender Details > **Tender Consolidated Details**

Tender ID: 184783	IFB/Tender Notice No.:HD-12/25	Description of Material/Name of Work: SWACHH BHARAT ABHIYAN PROVIDING VARIOUS SIGN BOARDS, DUSTBINS, OFFICES INSIDE CARGO JETTY AREA AND SOLID WASTE MANAGEMENT
ECV (INR):26743317.00	Last Date For Bid Submission: 19-06-2025 12:00	Tender Type/Tender Category :Open/WORKS
Location: Kachchh	Department: Deendayal Port Authority	Sub Department: Town Development Division

## View Tender Items

BOQ || View All Subwork

BOQ

Item No.	Item Description	Qty	Unit
1	Removal of Garbage/debries by mechanical means (Hydraulic excavator)/manual means by providing one JCB, two Tractor with trolley and 4 nos labour through out day shift over areas including getting out and disposal of stuff lead upto 5.00 KM outside cargo jetty area, as directed by Engineer-in-charge.	16300.890	M3
2	Supply and erection of Twin Plastic Container bins of 100 litre capacity each separate for wet & dry waste material along with MS stand made of MS square box pipe of 50mm with 4mm thickness including loading unloading transportation and fixing at site by concrete pedestal 500x500x800mm on both legs by excavating/breaking the surface at various locations inside / outside cargo jetty area, complete all the cost of material, labour, as directed by Engineer in charge.	200.000	Nos.

Item No.	Item Description	Qty	Unit
3	Collecting of garbage including loading, unloading of garbage from dustbins from various locations / Solid waste / Civil waste by garbage tank mounted on diesel truck of 5 tonne capacity including the cost of diesel, hire charges of truck, labours 4 nos, to be collected from inside/outside cargo jetty and disposal of the garbage at designated location i.e New Shamashan Bhoomi (Crematorium) at Gandhidham and etc. complete including all the cost of material, labour as directed by Engineer in charge.	1440.000	Per Trip
4	Plastering with cement mortar 1 : 4 including racking out joints, scrubbing & cleaning, finishing smooth curing including racking out joints etc. complete for interior plastering upto floor two level. (a) 12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	1540.000	M2
5	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : (a) Water thinnable cement primer	3080.000	M2
6	Floor painting with floor enamel paint of approved brand and manufacture of required colour to give an even shade : (a) Two or more coats on new work	3080.000	M2
7	Lettering with black Japan/ Synthetic enamel/ floor enamel/ enamel paint of approved brand and manufacture as directed by engineering incharge.	5000.000	per letter per cm height

Item No.	Item Description	Qty	Unit
8	<p>Manufacturing, supplying and fixing retro reflective overhead signage boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type - III of ASTM-D-4956-01 as approved by Engineer-in-charge, letters, borders etc. as per IRC : 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts &amp; nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with theft resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the consider 15 m2 of different size board corners, lowering down the structural frame work from the gantry, fixing and erecting the same in position by providing Cement concrete 1: 1 1/2 :3 pedestals of side 600x600x1000mm for supports all complete as per specification and direction of the engineer-in- charge. (Structural frame work including M.S.</p>	110.700	M2

Item No.	Item Description	Qty	Unit
	plate to be provided separately. Rectangular area of the sheet only shall be measured for payment).		
9	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	3321.000	KG
10	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete.	7332.100	M2
11	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	332.100	M2

Item No.	Item Description	Qty	Unit
12	<p>Providing and operating mechanically operated hydraulic tractor mounted Road Sweeping Machine (Broomer) for cleaning and sweeping of roads, berms area surrounding godowns, plots and area wherever as directed by Engineer- In-Charge. The work includes deploying of 06 Nos. (Six) of tractor moulded sweeping machine (with PVC broomers only) including engaging operators and sufficient labours for collecting of swept material, collection, loading disposal of swept material within lead of 5 km outside cargo jetty area including dressing the material at disposal site. The rates quoted includes all the charges for deploying sweeping machine, engaging labour, fuel charges, loading &amp; disposal of swept material as directed by Engineer-In-Charge.</p>	43700333.000	M2

## Notes

Subwork Name	Description	Period of Completion	Scope of Subwork
BOQ	As per Tender	24.0	As per Tender

BACK