



## Tender Details

Tender Details > **Tender Consolidated Details**

Tender ID: 185107	IFB/Tender Notice No.:HD-06/25 (Reinvited)	Description of Material/Name of Work: PROVIDING CATTLE TRAPS AT GATES OF CARGO JETTY AREA
ECV (INR):3409853.00	Last Date For Bid Submission: 29-05-2025 12:00	Tender Type/Tender Category :Open/WORKS
Location: Kachchh	Department: Deendayal Port Authority	Sub Department: Town Development Division

## View Tender Items

BOQ || View All Subwork

BOQ

Item No.	Item Description	Qty	Unit
1	Demolishing R.C.C. work manually/ by mechanical means including taking away of steel bars/ scrape MS structure and disposal of unserviceable material within 2 km lead as per direction of Engineer - in-charge.	33.000	m3
2	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. a) All kinds of soil / GSB Filled Area / Asphalted surface	133.000	m3
3	Supplying and filling in plinth with sand in layer not exceeding 200mm thickness under floors, including watering, ramming, consolidating and dressing complete.	28.000	m3
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : a) 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size).	28.120	m3

Item No.	Item Description	Qty	Unit
5	Providing and laying in position machine batched and machine mixed 1:1.5:3 ratio Reinforced cement concrete for reinforced cement concrete work, using cement content @ 395 kg/m <sup>3</sup> , including placing/pouring of concrete to site of laying also including the cost of centering,shuttering, finishing, vibrating, levelling, curing etc., as per direction of Engineer-in-charge.“ for work below plinth. (Rate is exclusive of cost of reinforcement)	99.900	m <sup>3</sup>
6	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete upto plinth level. a) Thermo-Mechanically Treated bars of grade Fe- 500D or more.	8880.000	Kg
7	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	33.000	m <sup>3</sup>
8	Extra rate for conveying the excavated stuff by motor - truck. a) Lead upto 3.50 BEYOND 3.00 KM	100.000	m <sup>3</sup>
9	8 mm cement plaster finished with a floating coat of neat cement of mix : a) 1:3 (1 cement: 3 fine sand)	185.000	m <sup>2</sup>

Item No.	Item Description	Qty	Unit
10	Providing & Fixing Cattle trap as per the Technical Specification: Fabrication work by structural steel member i.e. ISMB, Angles, Channels, Plates, etc. with Galvanized Iron Pipes Heavy duty, along with necessary Ball Bearing on end of Pipes, so that pipes can rotate and fixtures made in lathe machine to anchor the pipes on top of ISMB, including all the cost of cutting bending welding with welding roads, all machinery, labour, etc. The work includes loading unloading transportation and fixing on the RCC wall complete as directed. The work of construction of RCC Pit will be paid separately.	23113.900	kg
11	Finishing with Epoxy paint (two coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete.	799.200	m2
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	799.200	m2

## Notes

Subwork Name	Description	Period of Completion	Scope of Subwork
BOQ	As per tender	12.0	As per tender

[BACK](#)