

दीनदयाल पत्तन प्राधिकरण  
**DEENDAYAL PORT AUTHORITY**



Office of the Executive Engineer (H),  
Harbour Division, Nirman Building  
New Kandla- 370201  
Kachchh (Gujarat)  
Email: [kphdivision@gmail.com](mailto:kphdivision@gmail.com)  
[www.deendayalport.gov.in](http://www.deendayalport.gov.in)

\*\*\*\*\*

No: HW/WK/2645

Date: 06/06/2025

To,

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

**Expression of Interest.**

**Sub:- Two Years Maintenance Contract for Office buildings outside Port area  
(Civil Work)**

R/Sir,

Deendayal Port Authority intends to carry out the subject work of Harbour Division of Civil Engineering Department for a period of 24 months.

Kindly submit your Expression of Interest along with budgetary offer for the items considered in preparation of the estimate under **Annexure-A**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work, Contractor's Profit. The rates shall be exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your expression of interest along with budgetary quotation for the above work should reach to the following address on or before **13/06/2025 by 12:00 Hrs.**

**Address:-**

Office of the Executive Engineer (H),  
Harbour Division, First Floor,  
Nirman Building, New Kandla,  
Kutchh (Gujarat)  
Email :[kphdivision@gmail.com](mailto:kphdivision@gmail.com)

Thanking you,

Yours faithfully,

Sd/-

**Executive Engineer (H)  
Deendayal Port Authority**

**BUDGETARY QUOTATION**

**Name of Work :**     **Deployment of equipment for cleaning of all toilet block and rest shelters inside port area to maintain high standard of hygienic and to avoid pollution.**

<b>Sr.No.</b>	<b>Description</b>	<b>Unit</b>	<b>Rate</b>
1	Solid block 400 x 200 x 150 mm thick with loading, unloading transport and royalty at Kandla	Each	
2	Anti corrosive Paint Fosroc nitozinc	Litre	
3	Providing 6mm thick multiwall poly carbonate sheet	Sqm	
4	Supplying Full body Vetrified Tiles at Kandla	Sqm	
5	Providing, laying & jointing uPVC pipes of required working pressure as per I.S.I. including cutting and jointing the pipe ends as per manufacturer's instructions including the cost of all the specials plain & brass threaded fittings wherever required and, excavation and refilling of the trenches or fixing on walls or similar structures with clamps and testing the joints etc., complete as directed.		
	(a) 15 mm dia.	Rmt	
	(b) 20 mm dia.	Rmt	
	(c) 25 mm dia.	Rmt	
	(d) 32 mm dia.	Rmt	
6	Repairing , Rewinding, Servicing of monoblock/ submercible water pumps various capacity including removing and Refixing and replacement of all the required spare parts i.e. mortar winding, capaciter, bearing etc. complete as directed by Engineer-In-Charge.		
	(a) 0.5 HP to 2 HP Capacity	Each	
	(b) 3 to 5HP Capacity	Each	
7	Supplying & fixing of monoblock motor pump of different capacity of approved quality with necessary fittings, making electrical connections, testing etc. complete as directed by the Engineer In-charge		
	(a)0.5 HP Capacity	Each	
	(b) 1 HP Capacity	Each	
	(c ) 3 HP Capacity	Each	
	(d) 5 HP Capacity	Each	
8	Providing & fixing SWR PVC (I.S.I - IS 13592) waste or vent pipe including necessary specials such as Tees, Bends, Y's Plinth offsets, Shoes , Vent cowl etc. with bracket , screws on wooden plugs fixed on wall face including filling joints with solution & cement mortar 1:2 complete as directed.		
	(a)75 mm dia. (Outer Dia)	Rmt	
	(b)110 mm dia. (OD)	Rmt	
9	Supplying & fixing the following fixtures of Stainless Steel of approved quality to the doors, windows, ventilators etc. complete as directed by Engineer-in-Charge.		
	(a)Handle 100 mm size.	Each	
	(b)Aldrop 300 x 16 mm size	Each	
	(c)Mortice Lock (handle)	Each	
10	Operating of various capacity water pumps for pumping of fresh water from under ground water tanks to overhead		

	water tanks at various location of office buildings including operating of valves by with necessary Transportation Vehicle, operator and communication means etc. as directed by Engineer-In-Charge	Per Days	
11	Deployment of Tractor with tractor trolley including labours for removing of solid waste/ Garbage/Debris material and disposing the same outside of cargo jetty area. The rates are including tractor trolley and labours, loading, unloading & lead up to 3 Km out side cargo jetty area.	Trip	
12	Providing and fixing louvers Roller blinds (curtains) for windows made up of approved make and color with guide channel & chain with pull & push arrangement including cost of brackets, screws etc. with all labour, materials complete as directed by Engineer-In-Charge.	Sqm	
13	Providing and fixing the system for ornamental elevation made up of Aluminium Composite Panels with 3.25mm thickness with '3M' brand PVDF coated two way tape to fix the ACP with required aluminium Framed structure - made out of 1.2mm thick aluminium channels/Box section of weight not less than 2 kg/Length - fixed rigidly with the existing wall using suitable fasteners and neatly finishing the joints by the process of DOW corning using all weather sealant of grade '995' silicon including finishing sharp edges, M.S. structure framing, cutting, fixing, etc. complete with all labour and material as directed.	Sqm	
14	Providing and fixing of glass cladding with the 5mm saint gobain (or equivalent) sapphire blue glass/ or colour glass, 2(1/2)" x 1 (1/2)" pipe (38mm x 63mm of 2.0 mm thickness) , powder coating & colour anodizing with required necessary fixtures like measure tape, aluminium stud, abro tape etc. complete with all labour and material.	Sqm	
15	Providing cement based water proofing layer on Terrace over IPS flooring/Concrete, in required slope to drain the water for any span after cleaning the base surface and providing with average 25 mm thick layers of C.M.1:3 added with jute fiber at 1 Kg per bag including finishing the surface smooth with cement slurry admixed with approved water proofing compound. Making the junctions at the parapet rounded and tapered top for required height, with drip mould at the junction of plaster and parapet including Providing & Laying tile small pieces in mosaic pattern ( China Mosaic Tile Flooring ) on top layer of waterproofing treatment, over cement slurry, to desired slope, including conveying, lifting of material, curing, labour etc. complete as directed by Engineer in Charge	Sqm	

**Note :** The rates are excluding of GST.

**Sd/-**

**Signature of Contractor  
with seal**

**EXECUTIVE ENGINEER (H)  
DEENDAYAL PORT AUTHORITY**

**Place : \_\_\_\_\_**

**Date : \_\_\_\_\_**