

CONSTRUCTION-I DIVISION

DEENDAYAL P O R T A UTHORITY

ISO 9001-2008 Certified Port

Office of the Executive Engineer (C-I),

303, A.O Building Gandhidham (Kachchh)

Gujarat. PIN 370201.

Email :constdiv1@gmail.com



CN-I/WK/ 3053/

Date:- 16.07.2025

To,

Expression of Interest

Sub: **PROVIDING COMMON APPROACH ROAD CONNECTIVITY FOR PROPOSED GREEN HYDROGEN PLOTS AT PADANA**

Sir,

Deendayal Port Authority intends carry out the work for **PROVIDING COMMON APPROACH ROAD CONNECTIVITY FOR PROPOSED GREEN HYDROGEN PLOTS AT PADANA**

Kindly submit your Expression of interest along with budgetary-offer as per the prescribed format i.e. Annexure-I.

The rates quoted must be exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your Expression of interest along with budgetary offer for the above work should reach to the following address on or before 21.07.2025

Thanking you,

Yours faithfully,

Encl. As above

sd/-
Executive Engineer (C-I)
Deendayal Port Authority

CONSTRUCTION - I DIVISION

Name of Work: PROVIDING COMMON APPROACH ROAD CONNECTIVITY FOR PROPOSED GREEN HYDROGEN PLOTS AT PADANA

Sr.No.	Description	QTY	Unit	Rate	Amount
1	Providing primary rock of 0.1 to 0.5T for road work/ground including cost of quarrying, royalty, loading, unloading, transportation and spreading in layers from existing ground to required level, levelling, dressing side slopes etc., complete with all labour and materials complete including settlement etc., as directed by the engineer in charge.	192000.00	MT		
2	Providing embankment for approach road with quarry spall / granular material material including cost of excavation, royalty, loading, unloading, transportation, spreading in layers, comaction with road roller 8 to 10 t capacity for remaining layers to achive the omc from existing ground to required level, levelling, dressing side slopes , watering over the layers as desired by EIC etc., along with spreading of dust over the surface complete with all labour and materials complete including settlement etc., as directed by the engineer in charge.	132750.00	m3		