


दीनदयाल पोर्ट प्राधिकरण

DEENDAYAL PORT AUTHORITY



Office of the Executive Engineer (H),
Harbour Division, Nirman Building
New Kandla- 370201
Kachchh (Gujarat)
Email: kphdivision@gmail.com
www.deendayalport.gov.in

No: HW/WK/ Date: 20/08/2025

To,

Expression of Interest.

Sub:- Construction of Toilet Blocks and Rest Shelters at Berth no. 1 to 10 and at Back up area of Cargo jetty area at New Kandla.

R/Sir,

Deendayal Port Authority intends to carry out the subject work of Harbour Division of Civil Engineering Department for a period of 24 months.

Kindly submit your Expression of Interest along with budgetary offer for the items considered in preparation of the estimate under **Annexure-A**.

The rates quoted must be inclusive of all taxes, duties for performing scope of work, Contractor's Profit. The rates shall be exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

Your expression of interest along with budgetary quotation for the above work should reach to the following address on or before 27/08/2025 by 15:00 Hrs.

Address:-

Office of the Executive Engineer (H),
Harbour Division, First Floor,
Nirman Building, New Kandla,
Kutchh (Gujarat)
Email : kphdivision@gmail.com

Thanking you,

Yours faithfully,

slr

**Executive Engineer (H)
Deendayal Port Authority**

BUDGETARY QUOTATION

Sr.No.	Description	Qty.	Unit	Rate
1	Reclamation of area for plot & approach road with mechanical plants equipments with quarry spall not exceeding 125 mm th. Including cost of excavation royalty taxes loading, unloading, transportation, spreading to required level, levelling, dressing in a layer of not more than 300 mm etc. & wet consolidation by loaded trucks movement and at top with power vibratory roller etc. complete with all labour and material as directed by Engineer-in-charge.	3763.00	m3	
2	Supplying & fixing the following fixtures of approved quality to the doors, windows, ventilators etc. complete as directed by Engineer-in-Charge. (a) Aldrop 300 x 16 mm size	69.00	Each	
3	Supplying, testing, commissioning RO Plants of 150 Litre per hour capacity (including PVC water tank of 500ltr capacity) of approved make which consists of all necessary parts viz motor pump of required capacity, multipart valve, 20" bowl & filter silver process of high pressure pump of required capacity, multipart valve, 20" bowl & filter silver process of high pressure pump of required capacity, membrane, Rotameter, pressure meter, electric panel with M.S. Cabinet all necessary Electric & other connection required to commissioned the RO Plant which gives the required TDS complete with loading, unloading & Transportation, Installation including all taxes with one year warrantee and maintenance free.	7.00	Each	
4	Collection, and filling Black stone dust / Grit in foundation and trenches in a layer of avg 20 cm including cost of Excavation ,Royalty, loading, unloading and transportation at the site of work.	1479.00	m3	

Note : The rates are excluding of GST.

Signature of Contractor
with seal

Place : _____

Date : _____

SLD. 
EXECUTIVE ENGINEER (H)
DEENDAYAL PORT AUTHORITY