

CONSTRUCTION-I DIVISION



DEENDAYAL PORT AUTHORITY
ISO 9001-2008 Certified Port
Office of the Executive Engineer (C-I),
303, A.O Building Gandhidham(Kachchh)
Gujarat. PIN 370201.
Email : constdiv1@gmail.com
Website : deendayalport.gov.in

CN-I/WK/

Date: - 07/08/2025

To,

Expression of Interest

Sub:- **Construction of Service Road from jungi/vadhiya to village veera for Demarcation and safe Guard of DPA land bifurcating state government land(Phase-1)-EOI**

Sir,

Deendayal Port Authority intends to the work of **Construction of Service Road from jungi/vadhiya to village veera for Demarcation and safe Guard of DPA land bifurcating state government land (Phase-1)-EOI**

In this regard, Expression of interest along with budgetary-offer as per the prescribed format are enclosed hereby at Annexure A.

The rates quoted must be exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

In view of above, it is requested to kindly submit the Expression of interest along with budgetary-offer.

Your Expression of interest along with budgetary offer for the above work should reach to the following address on or before 11/8/2025.

Address:

Executive Engineer (C-I),
303, New Annexe Building
Gandhidham. PIN 370201.
Email: constdiv1@gmail.com
Website: deendayalport.gov.in

Thanking you,

Yours faithfully,

Encl. As above

-SD-
Executive Engineer (C-I)
Deendayal Port Authority

Construction division -1

Name of work:- Construction of Service Road from jungi/vadhiya to village veera for Demarcation and safe Guard of DPA land bifurcating state government land(Phase-1)-EOI

Sr. No.	Description	Qty	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing embankment for approach road with quarry spall / granular material material including cost of excavation, royalty, loading, unloading, transportation, spreading in layers, comaction with road roller 8 to 10 t capacity for remaining layers to achive the omc from existing ground to required level, levelling, dressing side slopes , watering over the layers as desired by EIC etc., along with spreading of dust over the surface complete with all labour and materials complete including settlement etc., as directed by the engineer in charge. for road work	439320.00			M3.	
2	Providing primary rock of 0.1 to 0.5T for road work/ground including cost of quarrying, royalty, loading, unloading, transportation and spreading in layers from existing ground to required level, levelling, dressing side slopes etc., complete with all labour and materials complete including settlement etc., as directed by the engineer in charge.Level	659088.00			M3.	
				Total =	Rs.	

Note: The rate quoted shall be exclusive of GST.

Signature of Contractor

**Executive Engineer (C-I)
Deendayal Port Authority**