

SCHEDULE - B

Name of Work: Laying, spreading and compaction of staked quarry material at Kandla

Sr.No.	Description	Total Qty.	Rate		Unit		Amount
			In Fig	In Words	In Fig	In Words	
1	Laying, spreading, compacting and shifting of Quarry Spalls material with loading, unloading and transporting. The material shall be spread in uniform thickness and compacted in layers using vibratory rollers of 8 - 10 tonne capacity with Watering to achieve proper grade and camber. The work shall include consolidation to meet specified compaction values and surface accuracy, complete in all respects as directed by the Engineer - in - charge.						
		625000.00			M3	Cubic Meter	
					Total Rs.		

Contractor

Executive Engineer(C-I)
Deendayal Port Authority