

Schedule-B

Name of Work : CSR Request for repairing of School Shed, School Colour Work at Ganeshnagar Panchayat Prathmik Kumar Shala at Gandhidham.

Measurement Sheet							
It. No.	Description of Item.	Qauntity	Rates in (₹)		Unit		Amount in (₹)
			In Fig.	In Words	In Fig.	In Words	6
1	Filling in cracks upto average 10mm deep with chemical bonding with white cement. Including removal of loose material etc. Complete as Direct.	369			Rmt	Running Metre	
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	1292			Sqm	Square Metre	
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	719			Sqm	Square Metre	
4	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :New work (two or more coats) over and including water thinnable priming coat with cement primer	719			Sqm	Square Metre	
5	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work (Co-efficient 0.125 Litre/sqm)	232			Sqm	Square Metre	
6	Finishing walls with textured exterior paint of required shade : New work (Two or more coats applied @ 3.28 ltr/10 sqm) over and including priming coat of exterior primer applied @ 2.20kg/10 sqm	1068			Sqm	Square Metre	
7	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	575			Sqm	Square Metre	
	Total Amount						
	In words Rupees _____ only)						
	(NOTE: The rates should be inclusive of all taxes, duties, fees, cess etc. and all incidental charges; but exclusive of GST).						

**Seal & Sign of
Contractor**

**Executive Engineer (CSR)
Deendayal Port Authority**