


दीनदयाल पत्तन प्राधिकरण
DEENDAYAL PORT AUTHORITY

An ISO 9001:2000 Certified Port
(Ministry of Ports, Shipping & Waterways, Govt. of India)

Email: xenroadskpt@gmail.com



अधीक्षण अभियंता का कार्यालय (R)
Office of the Superintending Engineer (R)
उपभवन / Annexe Building
ए ओ बिल्डिंग पोस्ट बॉक्स न. 50
A.O. Building, Post Box No 50
गांधीधाम (कच्छ) / Gandhidham (Kutch)

No.RW/WK/EOI/ 930

Date : 31/10/2025

To,

-----,
-----,
-----,

EXPRESSION OF INTEREST

Sub: **Repairing of approach road from NHAI road to Mithirohar
GIDC via village road**

Sir,

Kindly submit your Expression of Interest (EOI) along with budgetary quotation offer for the subject work for the items considered for preparation of the Estimate under (Annexure-I)

The rates quoted must be inclusive of all taxes, duties for performing scope of work & Exclusive of GST. Applicable GST shall be shown separately, which shall not be considered for evaluation purpose.

Your Expression of Interest submit along with budgetary quotation for the above work should be reach to following address by Registered Post/Speed Post/ Courier on or before **07.11.2025 by 16:00 Hrs.**

Thanking you,

To,
Office of Superintending Engineer (R),
Room No. 103, A.O. Building Annexe
Deendayal Port Authority,
Gandhidham-Kutch-370201

Yours faithfully,


Superintending Engineer (R)
Deendayal Port Authority

Annexure-I

Sr. No	Description	Unit	Rate
1	Filling of approach road with quarry spall in layers of 200mm thick including cost of excavation royalty, taxes, loading, unloading, transportation spreading to required level, levelling, dressing in layers of 200mm each & wet consolidation by loaded trucks movement and at top with power vibratory roller 8 to 10 Tone capacity etc. complete with all labour, material & equipment as directed by Engineer-in-Charge.	M3	
2	Collection, spreading, watering and consolidation of stone dust/stone grit by power vibratory roller of required capacity in a layer of average 20mm thickness to fill the voids of quarry spall layer surface including the cost of excavation Royalty, loading unloading and transportation at the site of work.	M2	
		Total Rs.	