

CONSTRUCTION-I DIVISION



DEENDAYAL PORT AUTHORITY
ISO 9001-2008 Certified Port
Office of the Executive Engineer (C-I),
303, A.O Building Gandhidham(Kachchh)
Gujarat. PIN 370201.
Email :constdiv1@gmail.com
Website : deendayalport.gov.in

CN-I/WK/

Date: - 26.11.2025

To,

Expression of Interest

Subject:- **Up-gradation of Road from Junction of Tuna Jetty Road to take off point at Tuna Tekra -EOI reg.**

Sir,

Deendayal Port Authority intends to the work of **Up-gradation of Road from Junction of Tuna Jetty Road to take off point at Tuna Tekra.**

In this regard, Expression of interest along with budgetary-offer as per the prescribed format are enclosed hereby at Annexure A.

The rates quoted must be exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

In view of above, it is requested to kindly submit the Expression of interest along with budgetary-offer.

Your Expression of interest along with budgetary offer for the above work should reach to the following address on or before 01.12.2025

Address:

Executive Engineer (C-I),
303, New Annexe Building
Gandhidham. PIN 370201.
Email: constdiv1@gmail.com
Website: deendayalport.gov.in

Thanking you,

Yours faithfully,

Encl. As above

-SD-
Executive Engineer (C-I)
Deendayal Port Authority

Construction-I Division

Name of work:- Up-gradation of Road from Junction of Tuna Jetty Road to take-off point at Tuna Tekra -EOI

Sr. No.	Description	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	<i>Anti-Glare screen: Providing and erecting Safety Light Barrier Anti-Glare screen of dimension 1335 mm x 600 mm x 80 mm leaf shape of High durable virgin premium grade Polyethylene material (L.L.D.P.E.) resistant to wind load 6m/s, and good aging resistance. The fixing at site shall be in 1:2:4 CC block of size 30 x 30 x 40 Cms by drilling of 30 cm x 30 cm x 30 cm size in existing median and anchoring by 2 nos of 8 mm Dia Fe500 D Reinforcement Bar and Fixing Radium strip of 225 mm x 215 mm size both side including excavation, curing etc. complete Block for proper level and smooth surface below the ground and anti glare screen having clear the 1600mm height over the ground at every 1.5m c/c spacing, INCLUDING Labour Charges Fitting and Transportation at site. All Installation, fitting and material be as per instruction approved by the engineer in-charge at site.</i>	3300			Nos.	
				Total =	Rs.	

Note: The rate quoted shall be exclusive of GST.

Signature of Contractor

**-Sd-
Executive Engineer (C-I)
Deendayal Port Authority**