

SCHEDULE-B

Name of the work :- Dismantling of Jetty Office, Immigration office and Canteen no. 1 & 2 in Cargo jetty area at New Kandla.

CREDIT ITEM

Sr. No.	Description	Qty.	Rate		Unit	Amount
			In fig.	In words.	In fig.	
1	Demolition of framed structure building along with structure, office building, toilets, stores, stairs, from Ground level to 2nd floor level with RCC columns, beams, slabs, chajjas, lintels, plinth beams, steel trusses, purlins, A.C. sheets and balcony etc. including block/stone/brick masonry etc. and disposal of debris having lead up to 5.00 km outside custom bonded area. The dismantling/demolition shall be done by mechanical means i.e. Demolition machines or by using JCB/Hitachi, Pay loaders, Dumpers, Dozers, etc. or as directed by Engineer in charge. Nothing will be paid for demolition and disposal of the said structures/ buildings. The material like Jaffries, c.c. blocks, A.C. sheets, Doors/Windows Shutters & frames, electric fittings, wires, etc. received from the Buildings will be the Property of Contractor against demolition of the above said structure. The contractor has to offer an amount for taking away all the steel scrap material obtained from the dismantling/demolition of the said structure after deducting/considering the cost of demolition of the structure. The offer shall be including of demolition and disposal of debris/stuff including loading, unloading and transportation and levelling & dressing at designated site. A. Taking away all the steel scrap material obtained from dismantling/demolition buildings situated in cargo jetty area. Note: - Quantity calculated for all the steel scrap material obtained from dismantling/demolition is tentative. Contractor has to deposit the credit amount including taxes as per actual quantity retrieve of steel scrap material obtained from dismantling/demolition.	33430.00			Kg	

Total Credit Amount to be deposited to Deendayal Port Authority

XEN (H)

CONTRACTOR

Deendayal Port Authority