

CONSTRUCTION-I DIVISION



DEENDAYAL PORT AUTHORITY
ISO 9001-2008 Certified Port
Office of the Executive Engineer (C-I),
303, A.O Building Gandhidham(Kachchh)
Gujarat. PIN 370201.
Email :constdiv1@gmail.com
Website : deendayalport.gov.in

CN-I/WK/2283/

Date: - 12/05/2026

To,

Expression of Interest

Sub:- Construction of Service Road from jungi/vadhiya to village veera for Demarcation and safe Guard of DPA land bifurcating state government land(Phase-1)-EOI

Sir,

Deendayal Port Authority intends to the work of **Construction of Service Road from jungi/vadhiya to village veera for Demarcation and safe Guard of DPA land bifurcating state government land (Phase-1)-EOI**

In this regard, Expression of interest along with budgetary-offer as per the prescribed format are enclosed hereby at Annexure A.

The rates quoted must be exclusive of GST. The GST applicable shall be shown separately, which shall not be considered for evaluation purposes.

In view of above, it is requested to kindly submit the Expression of interest along with budgetary-offer.

Your Expression of interest along with budgetary offer for the above work should reach to the following address on or before 15/05/2026.

Address:

Executive Engineer (C-I),
303, New Annexe Building
Gandhidham. PIN 370201.
Email: constdiv1@gmail.com
Website: deendayalport.gov.in

Thanking you,

Yours faithfully,

Encl. As above

-SD-
Executive Engineer (C-I)
Deendayal Port Authority

Construction division -1

Name of work:- Construction of Service Road from jungi /vadhiya to village veera for Demarcation and safe Guard of DPA land bifurcating state government land(Phase-1)-EOI

Sr. No.	Description	Qty	Rate		Unit	Amount
			In Fig.	In Words		
1	Providing primary rock of 0.1 to 0.5T for road work/ground including cost of quarrying, royalty, loading, unloading, transportation and spreading in layers from existing ground to required level, levelling, dressing side slopes etc., complete with all labour and materials complete etc., as directed by the engineer in charge.	668832.00			MT	
2	Supplying and stacking of Quarry Spall /Granular Material for Embankment of Approach Roads/Plot with including cost of excavation, royalty, loading, unloading transportation complete with all labour and materials or as directed by Engineer in charge	841584.00			MT	
3	Laying, spreading, compacting and shifting of Quarry Spalls material with loading, unloading and transporting. The material shall be spread in uniform thickness and compacted in layers using vibratory rollers of 8-10 capacity with watering to achieve proper grade and camber. The work shall include consolidation to meet specified compaction values and surface accuracy, complete in all respects as directed by the EIC (200 mm to 300 mm layer wise)	525990.00			M3	
				Total =	Rs.	

Note: The rate quoted shall be exclusive of GST.

Signature of Contractor

**Executive Engineer (C-I)
Deendayal Port Authority**