

SCHEDULE-B

Sr. No.	Description	QTY	Rate		Unit		Amount
			In fig.	In words	In fig.	In words	
1	Providing primary rock of 0.1 to 0.5T for road work/ground including cost of quarrying, royalty, loading, unloading, transportation and spreading in layers from existing ground to required level, levelling, dressing side slopes etc., complete with all labour and materials etc., as directed by the engineer in charge.	289800.00			MT		
2	Supplying and stacking of Quarry Spall /Ganular Material for Embankment of Approach Roads/Plot with including cost of excavation, royalty, loading, unloading transportation complete with all labour and materials or as directed by Engineer in charge	686880.00			MT		
3	Laying,spreading,compacting and shifting of Quarry Spalls material with loading, unloading and tranasproting. The material shall be spread in uniform thicness and compacted in layers using vibratory rollers of 8-10 capacity with watering to achivce proper grade and camber. The work shall include consolidation to meet specified compaction values and surface accuracy,complete in all respects as directged by the EIC	429300.00			M3		
4	Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete						
	1200 dia Pipe	300.00			RMT		
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size).	125.00			M3		
						Total = Rs.	