

दीनदयाल पत्तन प्राधिकरण
DEENDAYAL PORT AUTHORITY

An ISO 9001:2000 Certified Port

(Ministry of Ports, Shipping & Waterways, Govt. of India)

दूरभाष / Tel 02836 223912
फैक्स / Fax 02836 220050
ई मेल seroadsdpa@gmail.com



Office of the Executive Engineer (T.D.)
उपभवन / Annexe Building
ए ओ बिल्डिंग पोस्ट बॉक्स नं 50
A O Building, Post Box No 50
गांधीधाम (कच्छ) / Gandhidham (Kutch)

No.TW/WK/7926

Date : 07/06/2026

To,

EXPRESSION OF INTEREST

Sub: **Renovation of STAFF ROOM of PR Cell at Room No, 117-A,
in Admin Building, Gandhidham.**

Sir,

Kindly submit your Expression of Interest (EOI) along with budgetary quotation offer for the subject work for the items considered for preparation of the Estimate under (Annexure-I)

The rates quoted must be inclusive of all taxes, duties for performing scope of work & Exclusive of GST. Applicable GST shall be shown separately, which shall not be considered for evaluation purpose.

Your Expression of Interest submit along with budgetary quotation for the above work should be reach to following address by Registered Post/Speed Post/ Courier on or before **07/06/2026 by 16:00 Hrs.**

Thanking you,

To,
Office of Executive Engineer (T.D.),
Room No. 103, A.O. Building Annexe
Deendayal Port Authority,
Gandhidham-Kutch-370201

Yours faithfully,


Executive Engineer (T.D.)
Deendayal Port Authority



Annexure-I

Sr. No	Description	Unit	Rate
1.	Providing and fixing of panel board for electric fixture with 0.23m height including 18mm plywood side top & bottom & 12mm plywood on front & 6mm plywood on backside on front plywood with 1mm bottom laminated sheet on top & sides, all the material should be used for approved quality brand & shed complete with cost of nails, fevicol, screws, taxes etc., of all labour & materials as directed by Engineer-in-charge.	m²	
2.	Providing and fixing 12 mm thick frosted glass partition between working tables including cost of "D" shape brackets, screws, making the edges of glass beveled on all sides, taxes complete with all labour and material.	m²	
3.	providing & fixing of louvers roller curtain on the windows with all necessary fixtures and all its accessories as per requirement and of approved colour and make complete with all labour and material etc. as directed by engineer in charge.	m²	
4.	Finishing & smoothing the wall surface with two coats of acrylic based cement putty of approved make & brand including and over the one of cement primer on new / old surface etc. complete all labour and material as directed by the Engineer-In-Charge.	m²	
5.	providing & fixing of executive 360' revolving chair with low back visitor chair and ss body base with	EACH	

	wheels & pneumatic up & down with one-point locking mechanism.		
6.	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & double acting hydraulic floor spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-in-charge including Door handle, lock and stopper etc.	m ²	
7.	Providing and laying/fixing Vinyl flooring 1mm thick as directed by the Engineer-in-charge.	m ²	
8.	Providing & fixing of Tag Board using backside 6mm thick plywood with covering Fabric including nails, fevicols & labour etc. complete as directed.	RMT	
9.	providing & fixing of artefacts ex. paintings, flower vase, wall pieces, etc. are placed/fixed as directed by engineer-in -charge	EACH	