

## **HARBOUR DIVISION**

**Name of Work : -Construction of pump room for fire fighting at cargo berth no. 10**

### **SCHEDULE - B**

Sr. No.	Description	Total Qty	Rate		Unit		Amt in Rs.
			In Fig.	In Words	In Fig.	In Words	
1	Providing and laying in position machine batched and machine mixed design mix M-30 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping of concrete to site of laying but including the cost of centering,shuttering, finishing and including admixtures in recommended proportions as per IS: 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge.	27.00			M3	One cubic metre	
2	Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete above plinth level.						
	Thermo-Mechanically Treated bars of grade Fe-500	3637.00			Kg	One kilogram	
3	Providing & laying cement concrete solid blocks1:8:6 (machine made) confirming to relevant IS(Latest Edition) masonry 200mm thick set in cement mortor 1:6 including curing etc. complete as directed. (A) In plinth /foundations/ super structure	29.00			M3	One cubic metre	
					Total Rs		

**Quotationer**

**Executive Engineer(H)  
Deendayal Port Authority**