



Tender Details

Tender Details > **Tender Consolidated Details**

| | | |
|-----------------------|--|---|
| Tender ID: 312810 | IFB/Tender Notice No.:HD-11/26 | Description of Material/Name of Work: Special Repairs to the road network by Resurfacing with Polymer Modified Bitumen inside cargo jetty area. |
| ECV (INR):96473316.00 | Last Date For Bid Submission: 10-06-2026 16:00 | Tender Type/Tender Category :Open/WORKS |
| Location: Kachchh | Department: Deendayal Port Authority | Sub Department: Town Development Division |

View Tender Items

Bill Of Quantity || View All Subwork

Bill of Quantity

| Item No. | Item Description | Qty | Unit |
|----------|---|-----------|------|
| 1 | Removal of Garbage/debries/waste cargo by mechanical means (Hydraulic excavator)/manual means over areas including getting out and disposal of stuff lead beyond 2.00 km upto 5.00Km outside cargo jetty area, as directed by Engineer-in-charge. | 25775.000 | m3 |
| 2 | Construction of granular sub - base by providing, laying, spreading and compacting CLOSE/ COARSE GRADED MATERIAL spreading in uniform layers with motor grader on prepared surface and compacting with power vibratory roller of required type and capacity to achieve the desired density including all labour, wattering, material , machinery, lighting, guarding, barricading complete as directed. (Mix in place method). With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30 | 5790.000 | m3 |

| Item No. | Item Description | Qty | Unit |
|----------|---|------------|------|
| 3 | Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with with motor grader in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. | 4825.000 | m3 |
| 4 | Providing and applying tack coat using bitumen emulsion conforming to IS: 8887, using emulsion pressure distributor including preparing the surface & cleaning with mechanical broom. With rapid setting bitumen emulsion (a) On W.B.M / W.M.M. @ 0.40 kg/sqm | 16125.000 | m2 |
| 4 | (b)On bituminous surface @ 0.25kg/sqm | 161250.000 | m2 |
| 5 | Providing and laying Dense Graded Bituminous Macadam using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge. 50 to 100 mm average compacted thickness with bitumen of grade VG-40 @ 5 percent (percentage by weight of total mix) and lime filler @ 2 percent (percentage by weight of Aggregate) prepared in drum Type Hot Mix Plant of 60-90 TPH capacity. | 2977.000 | MT |
| 6 | Providing and laying Bituminous concrete using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete and as per directions of Engineer-in-Charge. 40/50 mm compacted thickness with bitumen of grade PMB-76-10E @ 6.00 percent (percentage by weight of total mix) and lime filler @ 3 percent (percentage by weight of Aggregate) prepared in drum Type Hot Mix Plant of 60-90 TPH capacity. | 17096.000 | MT |

| Item No. | Item Description | Qty | Unit |
|----------|--|-----------|------|
| 7 | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil | 7880.000 | m3 |
| 8 | Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete. | 40.000 | m3 |
| 9 | Providing, laying and fixing in position upto 1 km lead design mix reinforced cement controlled concrete for RCC Precast slab / RCC Precast curbing of design mix M-30 grade cement concrete for reinforced cement concrete work, using cement content as per approved design mix, including pumping / placing of concrete to site of laying including the cost of centering, shuttering, finishing as per direction of Engineer-in-charge. (Rate is exclusive of cost of reinforcement) | 270.000 | m3 |
| 10 | Steel reinforcement for R.C.C. work including straightening, cutting,bending, placing in position and binding all complete upto plinth level. | 30000.000 | Kg |
| 11 | Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m. | 1970.000 | m3 |
| 12 | Extra rate for conveying the excavated stuff by motor - truck. a) Lead upto 3.50 BEYOND 3.00 KM | 5910.000 | m3 |
| 13 | 12 mm cement plaster finished with a floating coat of neat cement of mix : 1:3 (1 cement: 3 fine sand) | 7238.000 | m2 |
| 14 | Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer | 10663.000 | m2 |
| 15 | Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work | 10663.000 | m2 |

| Item No. | Item Description | Qty | Unit |
|----------|--|-----------|------|
| 16 | Providing and laying factory made chamfered edge Cement Concrete paver blocks In foot path, park & lawns driveway or light & traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of course sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand, all complete as per manufacturer's specifications & 60mm thick Cement concrete paver block of M-35 grade with approved colour, design & pattern. | 19300.000 | m2 |
| 17 | Providing and fixing Glow studs of size 100x20 mm made of heavy duty body shall be moulded ASA (Acrylic styrene Acryloretrite) or HIP (High impact polystyrene) or ABS having electronically welded micro-prismatic lens with abrasion resistant coating as approved by Engineer in charge. The glow stud shall support a load of 13635 kg tested in accordance with ASTM D4280. The slope of retro- reflective surface shall be 35 (+/-5) degress to base.The reflective panels on both sides with at least 12 cm of reflective area up each side. The luminance intensity should be as per the specification and shall be tested as described in ASTM I: 809 as recommended in BS: 873 part 4 : 1973. The studs shall be fixed to the Road surface using the adhesive conforming to IS, as per procedure recommended by the manufacturer complete and as per direction of Engineer-in-charge. | 8766.000 | each |
| 18 | Providing and applying 2.5 mm thick road marking strips (retro-reflective) of specified shade/ colour using hot thermoplastic material by fully/ semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in- charge and accordance with applicable specifications. | 4855.000 | m2 |

| Item No. | Item Description | Qty | Unit |
|----------|---|-----------|------|
| 19 | Providing and fixing signs board with a corrosion resistance 2mm thick aluminium alloy sheet with high intensity peismatic (HIP) grade retro reflectivesheet, including fixing on structure as directed including lettering overhead sign etc complete all laboursand materials as directed by engineer-in-charge (excluding cost of frame work). | 226.000 | m2 |
| 20 | Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a epoxy based priming coat of approved steel primer all complete. | 23560.000 | Kg |
| 21 | Finishing with Epoxy paint (two coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. | 1178.000 | m2 |
| 22 | Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture | 1178.000 | m2 |

Notes

| Subwork Name | Description | Period of Completion | Scope of Subwork |
|------------------|---------------|----------------------|------------------|
| Bill of Quantity | As per Tender | 0.0 | As per Tender |

BACK