

DEENDAYAL PORT AUTHORITY
OFFSHORE OIL TERMINAL, VADINAR
EXPRESSION OF INTEREST

EOI No: OOT/C-RM/

Dated: / /2026

Subject: - Strengthening of Overhead Water tank at port colony Vadinar.

(This Notice is issued only to elicit Expression of Interest from the parties interested in the work and does not constitute any binding commitment from the DEENDAYAL PORT AUTHORITY to proceed with the work or invite any or all the parties in the subsequent bidding process. Public Tenders will be issued subsequently)

SECTION – I

DEENDAYAL PORT AUTHORITY (DPA) invites expression of interest from the Registered Civil Contractors and having experience of Civil Works for **“Strengthening of Overhead Water tank at port colony Vadinar.”** The expression of interest can be downloaded from Port website www.deendayalport.gov.in.

The works consist of **Strengthening of Overhead Water tank at port colony Vadinar..**

Strengthening of Overhead tank by micro concreting, bond coat applying, anti-corrosive treatment to steel, shear key of 8mm dia. for steel, painting with exterior paint, M.S. Structure, etc has been considered. The item(s) with description are provided in **ANNEXURE – II**

The party shall submit quotation in the format provided at Annexure-II.

How to Apply: Interested Parties are requested to submit EOI not later than 1500 hours IST on / /2026.

Details of the Party [ies] shall be filled as per Annexures and submit :

- Name and Address.
- Contact person[s] along with contact details, and

Documents to be submitted

- 1. Form – A – [Application]**
- 2. Annexure – I [Particulars of Firm]**
- 3. Annexure – II [Budgetary Offer]**

Suggestions

The Firms may also submit their suggestions and views, if any, that can be considered for the Project, in a separate sheet.

Address for communication:

Executive Engineer (C),
Administration Office Building,
Offshore Oil Terminal,
DEENDAYAL PORT AUTHORITY,
Vadinar, Dev Bhoomi Dwarka - 361010.
Tel: 0288-257301
Email: kptootcivilame@gmail.com

SECTION – II

Form - A

LETTER OF TRANSMITTAL (To be typed in Firm's Letterhead)

To

The Executive Engineer (C)
Administration office Building,
Offshore Oil Terminal,
Deendayal Port Authority,
Vadinar, Dev Bhoomi Dwarka – 361010.

Subject: - Strengthening of Overhead Water tank at port colony Vadinar.

Sir,

Having examined the details given in EOI Notice and EOI document for the above project, I/we hereby submit our Expression of Interest and the relevant information.

1. I/We hereby certify that all the statements made and information supplied in the enclosed form and accompanying statements are true and correct.
2. I/We have furnished all information and details necessary for EOI and have no further pertinent information to supply.
3. I/We also authorize DEENDAYAL PORT AUTHORITY or their authorized representatives to approach individuals, employers and firms to verify our competence and general reputation.
4. I/We submit the following certificates in support of our suitability and capability for having successfully provided the services along with prescribed format.
5. We understand that DPA will be at liberty to finalize requirements and issue public tenders for the work.

Thanking you

Signature(s) of Applicant(s)

Enclosures:

Seal of applicant:

Date of submission:

Annexure – I

Name of firms/Applicants

(Organizational Structure)

1	Name & Address of the applicant with Telephone No./Fax No	
2	a) Year of Establishment	
	b) Date & Year of commencement	
	c) Legal status of the applicant (attach copies of original document defining the legal status)	
3	a) A proprietary firm	
	b) A firm in partnership	
	c) A limited company or Corporation/ Joint venture / Consortia	
	d) State owned	
4	Any other information considered necessary but not included above	
5	PAN Number	
6	GST Registration Number	
7	Provident Fund Certificate Number	

Signature with Seal

Annexure – II

No	Description	Qty	Unit	Qouted rate/ Unit		Amount	
				In fig	In words	In fig	In words
1	Removal of damaged concrete/plaster: Removing & Cleaning of existing concrete/plaster carefully by low impact high frequency hammer/or by manual chipping without damaging the existing concrete.(Mode of measurement-per Sqmt of breaking area of concrete.)	967.86	M2				
2	Rust convertor: Clean existing reinforcement with wire/rotary wire brush making the surface free from loose material, dirt, etc. complete, Apply alkaline rust converting primer-Eget ARUP/ Impermo 1002/ Optychem PAR on the rebars, including cleaning the reinforcement wire brushing to remove loose rust spalls. (Mode of measurement: per sqm of breaking area of concrete.)	967.86	M2				
3	Anticorrosive treatment to reinforcement: Application of anticorrosive chemical Eget ACORB / Impermo 1003/ tychem BOR on exposed reinforcement in two coats with time interval of minimum 4 hours between each coat. The application shall be done by brush. (Mode of measurement: per sqm of application area of concrete.)	967.86	M2				
4	Additional steel: Providing and fixing in position high yield steel deformed bar reinforcement to replace corroded bars of the existing RCC member or new bars within Microconcrete jacket portion, including cutting, bending, hooking, anchoring links and tying the bars with 10 SWG GI binding wire or welding if required.	13451.24	kg				
5	Jacketing by micro concrete: Providing,	156845.6	kg				

	pouring, compacting, levelling precisely micro concrete ShaliFix MC/ Verdhaio MC/Impermo 4003/OptyRE M40 or equivalent of suitable grade upto required thickness, maintaining a minimum clear cover of 30 mm to the outermost reinforcement; including necessary shuttering work.						
6	Guniting is applied to the Concrete surface by high Velocity Nozzle pump with the help of polymer modified mortar upto the 20mm avg thickness including apply bond coat & clear the surface before guniting as directed by engineering incharge.	303.30	M2				
7	Shear key connectors: Drilling holes in concrete of suitable diameter, providing and fixing 8 mm diameter High Yield Steel reinforcing bars at 300 mm c/c on the RCC surface projecting out of the concrete surface within the jacket portion.	14370	Nos				

Net Amount

Signature of contractor