

SCHEDULE B

Name of work: Construction of Compound Walls for Commercial Buildings on Reserved Plots in DPA Land at Apna Nagar NU 3 and Sector 1-A Gandhidham (Stage -II)

Sr. No	Description of Items	Quantity	Unit		Rate		Amount
			In Figure	In Word	In Figure	In Word	
1	Providing and fixing of precast RCC Compound wall of height 1.80 meter with coloumn of size 150mm x 150mm x 2400 mm at 1.8 meter c/c including excavation and CC 1:1 , 1/2:3 of size 600 x 600 x 400 mm including all material and labour as directed by the Engineer in-charge	339.24	m	Meter			
2	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 3 km and lift upto 1.5m. All kinds of soil.	2548.47	m ²	sqm			
3	Removal of garbages and waste etc. by tractor/trolley having 4.50 m ³ capacity with four labour, tools & plants. Rates inclusive of labour, tools & plants, tractor/trolley, driver & diesel etc. complete (as and when required) for lead upto 13 km from A.O. Building	12.00	Trips	Trips			
4	Manufacturing, supplying and fixing retro reflective overhead signage boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activate retro reflective sheet conforming to type-III of ASTM-D-4956-01 as approved by the Engineer in-charge, letters, borders etc. as per IRC: 67-2001 in silver white with blue colour background and with high intensity grade pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm along the periphery as well as in two vertical rows along with the resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet, including appropriate priming coat. The rate includes the cost of rounding of the corners, lowering down the structural framework from the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer in-charge. (Structural framework including M.S. plate to be provided seperately. Rectangular area of the sheet only shall be measured for payment)	7.50	m ²	sqm			
					Total Rs.		
TOTAL RS. IN FIGURE							
TOTAL RS. IN WORD							

CONTRACTOR

EXECUTIVE ENGINEER (T.D)
DEENDAYAL PORT AUTHORITY